

**SURVEY & REMONUMENTATION**

MAR 09 1998

**KENT COUNTY REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

Located In: Corner Code #

- |                                    |  |            |
|------------------------------------|--|------------|
| 1. Public Land Survey              | T <u>5N</u> R <u>9W</u>                | <u>L-1</u> |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u> |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u> |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u> |
| 2. Property Controlling in Section | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |
| 3. Miscellaneous Property in Sec.  | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 APR 29 AM 8:20  
REG. OF DEEDS  
*[Signature]*  
**9780**  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-1	1830	GLO	Mullett	Not Set
	1936	Kent Co. Wit.		Concrete Monument
	1981	LCRC #1625	Byl	Concrete Monument
	1985	LCRC #4105	Jonker	Set Kent County Monument
	1990	LCRC #5466	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 1/21/85 and was recorded per LCRC #4105.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker on Twp. line at midpoint of mile. Corner per Kent Co. Wit. and LCRC #1625 are for L-13, T6N, R9W. Corner was previously used as common.  
LCRC #4105 Kent Co. Mon. East 6.0'  
Nail & tag 16" Maple S65°E 64.57'  
Nail & tag 12" Maple S10°E 18.24'  
Nail & tag 10" Cherry N20°E 51.74'  
Nail & tag P. Pole N45°E 121.35'  
Nail & tag 10" Oak N80°E 66.73'  
LCRC #5466 Kent Co. Mon. East 6.0'  
Nail & tag 16" Maple S65°E 64.57'  
Nail & tag 12" Maple S10°E 18.27'  
Nail & tag 10" Cherry N20°E 51.76'  
Nail & tag P. Pole N80°E 121.35'  
Nail & tag 10" Oak N40°E 66.78'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1	Standard Kent County Monument		
	Nail & KC Remon. tag N. side 20" Maple	S65°E	64.57'
	Nail & KC Remon. tag E. side 16" Maple	S10°E	18.24'
	Nail & KC Remon. tag E. side 14" Cherry	N20°E	51.76'
	Nail & KC Remon. tag S. side new P. Pole	N80°E	116.40'
	Nail & KC Remon. tag NW side 18" Oak	N40°E	66.78'
	Kent Co. Mon. (L-13, T6N, R9W)	East	6.00'
	C/L E-W grav. rd. is 2'± North		



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077  
P.A. 345 1990 KENT COUNTY

Date 3/27/97

PEER APPROVED 3/27/97  
CHAIRMAN *[Signature]*