

**SURVEY & REMONUMENTATION**

MAR 03 1998

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

**KENT COUNTY**

(County)

Located In:

Corner Code #

1. Public Land Survey

T 5N R 9W L-5

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 OCT 14 AM 10:02  
REG. OF DEEDS  
*Luis Standa*

**10032**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on June 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- L-5 1830---GLO---Mullett---Set Post
- 1966---Williams & Works---Temp. Point at split of fences N-S, hits C/L of E-W road, and is 2.08' S. of Sec. line
- C/L I-beam fc. post N 24.75' C/L "L" fc. post S 24.75'
- 1973---LCRC #570---Spicer---Set "T" Iron at 1966 Temp. Point
- C/L I-beam fc. post N 24.75' CP Pole N45°E 46.43'
- NW cor. hse. fnd. S35°E 69.59' In C/L road & on line fences N-S
- 1984---Research---Exxel---Held "T" Iron per LCRC #570

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-5 Found 12" long Spike per the following witnesses:
- C/L I-beam fc. post N05°E 24.75' Nail in CP Pole N45°E 46.41'
- NW cor. hse. fnd. S25°E 69.63' NE cor. "L" fc. post S05°W 25.01'
- Spike is 2.06' S. of Sec. line (2.08' W&W 1966)

The Spike is accepted by me and is generally accepted by professional surveyors as the best available evidence of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-5 Set Standard Kent Co. Monument (Harrison) in place of the Spike
- C/L steel I-beam fence post N05°E 24.75'
- Set Nail & KC Remon. tag NW side CP Pole N50°E 46.41'
- NW corner house foundation S25°E 69.63'
- NE corner steel "L" fence post S05°W 25.01'
- Set Nail & KC Remon. tag SE side wood post S55°W 39.89'
- In C/L E-W asph. road ±.
- In line with fences N & S ±.



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 8/28/97

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 6/26/97  
CHAIRMAN *Fanny Hubert*