

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
1. Public Land Survey T5N R 9W	L-9
T R	
T R	
T R	
2. Property Controlling in Section S T R	
S T R	
3. Miscellaneous S T R	
S T R	

STATE OF MICHIGAN
SOCIETY OF REGISTERED SURVEYORS
RECEIVED FOR RECORD
97 OCT 14 AM 10:30
REG. OF DEEDS
W. J. Stand

10057

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on June 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- L-9 1830---GLO---Mullett---Set Post
---Williams & Works---No information
- 1950---Kent Co. Wit.---Hub & Iron (Later Mon. Box)
SW cor. Hdwl. NE 64.85' NW cor. Hdwl. ESE 60.85'
MBT SW 63.1' 22" Maple WNW 96.05' 24" Oak NW 77.8'
- 1974---LCRC #636---Bonnema---Iron in Mon. Box
30" Oak NNW 78.81' T. Pole ENE 71.09' Face curb NE 38.6'
Face curb SE 38.85' Face curb SW 38.85' Face curb NW 38.8'

P.A. 345 1990 KENT COUNTY,
PEER APPROVED 6/26/97
CHAIRMAN H. J. Huber

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-9 Found 1" Iron Pipe in Mon. Box per the 4 witnesses to face of curb per LCRC #636.
- All other witnesses gone
- 1/2 mile measurements S-W-E agree with Exxel & Rob Jonker

The 1" Iron Pipe in the Monument Box accepted by me and is generally accepted by professional surveyors as the best available evidence of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-9 Set Standard Kent Co. Monument (Harrison) in Mon. Box in place of the 1" Iron Pipe
- Set Nail & KC Remon. tag E. side 36" Oak N10°W 152.47'
- Set Nail & KC Remon. tag top of fence post N65°W 90.11'
- Top corner "L" Iron fence post (leaning slightly) S30°W 73.49'
- Top C/L concrete post S25°E 71.90'
- Set Nail & KC Remon. tag N. side P. Pole S80°E 217.24'
- On C/L Asph. Rd. N-S & E-W

Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 9/5/97

