

**SURVEY & REMONUMENTATION**

APR 27 1995

**COMMISSION**

Kent County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD

94 DEC 30 PM 12:06

*Luigi J. Jonker*  
 REG. OF DEEDS

For corners in

Kent County (County)	Located In: Bowne Twp.	Corner Code ##
1. Public Land Survey	T <u>5N</u> R <u>9W</u>	<u>L-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

7974

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert Jonker, in a field survey on December 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Not set in GLO survey  
 1944, Old Kent Co. wit. map - 1" Iron  
 1974, LCRC #636, D. Bonnema, PS#12679, Found iron in mon. box & checks with prev. witnesses  
 Took new witnesses:  
 SE corner house fnd. NW 116.82'  
 PK-side P.pole NNW 141.18' Jonker, 1992, Found boat spike in mon. box  
 PK-side P.pole E 41.04'  
 Fence corner post W 28.25'  
 SW corner fr. shed NE 40.85'  
 C/L B.T. West 1.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found boat spike in mon. box, raised over 1" iron by wit. per LCRC #636  
 Calculated intersection of  $\frac{1}{2}$  lines is 8.7'± South & 2.1'± East

P.A. 345 1990 KENT COUNTY

PEER APPROVED 12/15/94

CHAIRMAN *Harry Huber*

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Replaced with 4" standard K.C. Harrison monument in mon. box.

K.C. N&T N. side P. pole N 85° E 41.08'  
 K.C. N&T N. side 18" Boxelder N 90° W 49.42'  
 K.C. N&T NE cor. 24" Pine N 20° W 100.51'  
 SE corner house fnd. N 55° W 116.83'  
 C/L N-S road is 1' West  
 on line with fence to West



Signed by *Robert J. Jonker*  
 JONKER LAND SURVEYS, P.C.  
 Surveyor's Michigan License No. 21572

Date December 28, 1994