

**SURVEY & REMONUMENTATION**

**KENT COUNTY REMONUMENTATION**

**MAR 03 1998**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**  
**KENT COUNTY**

(County)	Located In:	Corner Code #
1. Public Land Survey	T 5N R 9W	M-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REG. OF DEEDS

*Handwritten signature*

97 APR 29 AM 8:20

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

9787

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Mar. 13, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-5	1830	GLO	Mullett	Set Post
		Kent Co. Wit.		1" Iron
	1973	LCRC #570	Spicer	Set "T" Iron
	1981	LCRC #2159	Jonker	Set Kent County Monument
	1994	LCRC #6999	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 9/17/81 and was recorded per LCRC #2159

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-5 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the "T" Iron in a steel pipe next to a stone he found. All check with LCRC #570 and previous survey information.

LCRC #2159		LCRC #6999	RR Spike	East	5.45'
Remon. tag P. Pole	S05°W	53.74'	Nail & tag P. Pole	S05°W	53.74'
Remon. tag 9" Tri. Elm	N59°W	83.39'	Nail & tag 12" tri. Elm	N59°W	82.84'
Vertical mark on dr. culv.	S67°W	48.59'	C/L street sign	N49°W	45.2'
C/L street sign	N49°W	45.2'	"X" top conc. dr. culv.	S67°W	48.93'
RR Spike	East	5.45'	"Hole" top of metal culv.	N20°E	127.06'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5 Standard Kent County Monument					
Nail & KC Remon. tag E. side P. Pole	S05°W	53.74'			
Nail & KC Remon. tag N. side 12" Tri. Elm	N59°W	82.93'			
C/L leaning street sign	N49°W	45.5'±			
"X" cut top of E. end conc. drive culv.	S67°W	48.93'			
"Hole" in top of E. end steel culvert	N20°E	127.06'			
RR Spike	East	5.45'			



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 3/27/97  
CHAIRMAN *Harry Hubert*