

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 OCT 14 AM 10:30
REG. OF DEEDS
W. J. Bond

10058

Register of Deeds Stamp & File Number

For corners in SECTION	Located In:	Corner Code #
KENT COUNTY		
(County)		
1. Public Land Survey	T 5N R 9W	M-10
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on June 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
M-10 1830---GLO---Mullett---Set Post
---Williams & Works---No information
---Kent Co. Wit.---No information
1988---Survey---Jonker---Established corner - set Capped Iron - per fences to West and South that fit old description of parcel 445.5' West and 990' South of corner.
Spike in 6" Cherry N20°W 91.91' Spike in 6" Elm S65°W 44.45'
Spike in 6" Cherry S25°W 91.48' N-S tree row 38' West
1996---Survey---Exxel---Capped Rerod - Witnesses simular to Jonkers ±
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-10 Did not find anything at corner - location is in cultivated field. Established corner per witnesses of Rob Jonker and tied into traverse. Location compares with measurements and angles of Jonker and Exxel.

The Location per surveys by Rob Jonker and Exxel Eng. is accepted by me and is generally accepted by professional surveyors as the best available evidence of the original corner.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 16/26/97
CHAIRMAN *Harry Huber*

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-10 Set Standard Kent Co. Monument (Harrison) at location described above.
Nail & KC Remon. tag SW side 12" Cherry N20°W 91.91'
Nail & KC Remon. tag SE side 10" Elm S65°W 44.45'
Nail & KC Remon. tag NW side 12" Cherry S25°W 91.48'
Capped Rerod on E-W 1/4 line @ RR R/W N89°57'15"W 38.81'
Rerod (offset iron) N83°36'15"W 41.10'
Rerod (offset iron) N82°02'50"W 34.98'
Monument is in cultivated field 18" below grade.



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 9/24/97