

**SURVEY & REMONUMENTATION**

MAR 03 1998

KENT COUNTY REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in  
**KENT COUNTY**  
(County)

Located In:	Corner Code #
1. Public Land Survey	T 5N R 9W M-13
	T R
	T R
	T R
	T R
2. Property Controlling in Section	S T R
	S T R
3. Miscellaneous Property in Sec.	S T R
	S T R

REG. OF DEEDS  
97 APR 29 AM 8:20  
STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

9791

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Feb. 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-13	1830	GLO	Mullett	Set Post
	1944	Kent Co. Wit.		Iron
	1978	LCRC #1131	VanKooten	1 1/2" Round Iron
	1981	LCRC #1715	Merdzinski	Set Kent County Monument
	1994	LCRC #7002	Byl	Kent County Monument
	1996	LCRC #9603	Jonker	Reset Kent Co. Mon. after road const.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 2/16/81 and was recorded per LCRC #1715

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker at the same position as set in 1981 by John A. Merdzinski in place of the 1 1/2" Round Iron & Shear Blades in Stone Pile he found. Round Iron, etc. checks with Kent Co. Wit. & LCRC #1131. Wits. from LCRC's #1715 & #7002 removed during const. LCRC #9603

Nail & KC Remon. tag NW side P. Pole	S60°W	56.52'	Top of NW cor. steel
Nail & KC Remon. tag N. side G. Pole	N33°W	39.10'	guard rail post
Nail & KC Remon. tag SE side P. Pole	N44°E	36.90'	S19°W 63.24'
C/L base of street sign	S63°E	48.3'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13 Standard Kent County Monument			
Nail & KC Remon. tag NW side P. Pole	S60°W	56.52'	
Nail & KC Remon. tag N. side G. Pole	N33°W	39.10'	
Nail & KC Remon. tag SE side P. Pole	N44°E	36.90'	
C/L base of street sign	S63°E	48.30'	
Top of NW cor. steel guard rail post	S19°W	63.24'	
At C/L of intersection			



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 3/27/97  
CHAIRMAN Harry Ruben