

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

"other" code #s

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

Located In: Corner Code #

- 1. Public Land Survey

T	_____	R	_____
T	_____	R	_____
T	_____	R	_____
T	_____	R	_____
- 2. Property Controlling in Section

S	23	T	5N	R	9W	Wit. Mon. on
S	_____	T	_____	R	_____	N-S 1/4 line
- 3. Miscellaneous Property in Sec.

S	_____	T	_____	R	_____
S	_____	T	_____	R	_____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

97 OCT 14 AM 10:30

REG. OF DEEDS

Lucy Bond

10055

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on July 23, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

No Information - Not Set

See LCRC # 10053 for Central 1/4 corner (J-8) of Sec. 23

P.A. 345 1990 KENT COUNTY
PEER APPROVED 8/28/97
CHAIRMAN Harry Ruppel

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Established 1/8 corner South of Central 1/4 corner on North-South 1/4 line

East & West fence is South 4' - No occupation North & South

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Harrison Monument with witness cap at said 1/8 corner as described above

- Nail & KC Remon. tag NE side 15" Cherry S45°E 7.15'
- N. face of 3" steel fence post (stump) S10°E 4.46'
- N. face of post of golf ball washer S20°W 20.36'
- Nail & KC Remon. tag NW side 15" Cherry S75°W 7.22'
- E-W fence is South 4'±

On tree row E-W - Cultivated field North - Golf Course South

Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 9/5/97

