

SURVEY &
REMONUMENTATION

FEB 14 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in: Caledonia Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>10W</u>	<u>A-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

96 NOV - 8 AM 9:16

REG. OF DEEDS
9440

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on January 24 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-11	1831	G.L.O. Notes	Mullett	Set Post
	1952	Witness Map	K.C. Surveyor	1" Iron in Mon. Box
	1964	Notes	Williams & Works	Monument Box
	1983	L.C.R.C. #3574	William Byl	Fnd. 1" Iron in Mon. Box / Set K.C. Monument in Mon. Box
	1991	L.C.R.C. #5930	William Byl	K.C. Monument in Mon. Box
	1994	L.C.R.C. #7145	Glaza & Associates	K.C. Monument in Mon. Box

Note: This corner is not common with M-11, T5N, R11W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 9/28/83 and was recorded per L.C.R.C. #3574.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-11 Found a Standard Kent County Monument 5' South of the C/L of 100th Street (bit.) running East and West and on the C/L of Patterson Avenue (bit.) running North and South per L.C.R.C.'s #3574, #5930 and #7145 as set by William Byl in place of a 1" iron he found in a monument box which checked the 1964 notes of Williams & Works and the K.C. Surveyor's records.

L.C.R.C. #3574

L.C.R.C. #7145

Nail & tag, E sd. Power pole S 20° W 124.25'

Nail & tag, E sd. Power pole N 30° W 64.86'

NW cor. brick veneer, Hse. # 4802 S 30° E 133.80'

NE cor. brick veneer, garage of Hse. #4802 S 50° E 185.70'

NE cor. Sec. 36, 5-11 (Kent County Monument) N 00° E 11.87'

Nail & K.C. remon tag in E side P. pole S 20° W 124.19' (m. 124.24')

Nail & K.C. remon tag in W side P. pole N 30° W 64.84' (m. 64.79')

NW corner brick veneer house #4802 S 30° E 133.76' (m. 133.72')

NE corner brick veneer garage of house #4802 S 50° E 185.62' (m. 185.60')

Nail & K.C. remon tag in NW side light pole S 35° W 41.28' (m. 45.10')

NE corner concrete slab of MBT pedestal S 40° W 65.62' (m. 55.67')

NE corner, Sec 36, 5-11 (Kent County Monument) N 00° E 11.87' (m. 11.84')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11 Standard Kent County Monument

- Nail & K.C. remon. tag on SE side 8" Trip. Elm N 29° E 114.42'
- NE corner brick veneer garage of house #4802 S 50° E 185.60'
- NW corner brick veneer house #4802 S 30° E 133.72'
- Nail & K.C. remon tag in E side P. pole S 20° W 124.24'
- NE corner concrete slab of MBT pedestal S 40° W 55.67'
- Nail & K.C. remon tag in NW side light pole S 35° W 45.10'
- Nail & K.C. remon tag in W side P. pole N 30° W 64.79'
- M-11, T5N, R11W (Kent County Monument) N 00° E 11.84'

Signed by Randy J. Kolehouse Date 10/8/96

EARTHTECH

Surveyor's Michigan License No. 25854

P.A. 345 1990 KENT COUNTY

PEER APPROVED 17/25/96

CHAIRMAN James M. Hubert

