

FEB 14 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Table with columns: Kent (County), Located in: Caledonia Township, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

4. Lot No. , Recorded Plat
5. Private Claims

I, Randy Kolehouse, in a field survey on April 5 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with columns: B-13 1817, G.L.O. Notes, L. Lyon, Set Post, 1974, L.C.R.C. #639, Exxel Engineering, RR Spike, 1983, L.C.R.C. #3212, Williams & Works, Set K.C. Monument from L.C.R.C. #639 Witnesses, 1991, L.C.R.C. #5938, William Byl, K.C. Monument

Note: This corner is not common with B-1, T4N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 3/29/83 and was recorded per L.C.R.C. #3212.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13 Found a Standard Kent County Monument 1' North of the C/L of 108th Street (bit.) running East and West on line of a fence running North per L.C.R.C.'s #3212 and #5938 as set by Williams & Works from the witnesses provided in L.C.R.C. #639 as the RR spike had been graded out.

L.C.R.C. #3212

L.C.R.C. #5938

Nail & KC. Remon. tag in N'y side P. Pole S. 67° W. 95.25'
Nail & KC. Remon. tag in top C/L cor. fence post North 26.83'
Nail & KC. Remon. tag in S. side Triple 8" Ash N. 55° E. 78.75'
NE corner conc. block garage S. 25° W. 138.04'
On fence line running North - Brush row running South is 12' more or less East

Nail & KC Remon. tag N'y side P. Pole S 67° W 95.25'
Nail & KC Remon. tag W. side cor. fence post N 00° E 28.77'
Nail & KC Remon. tag S. side Tri. 10" Ash N 55° E 78.70' (m. 78.67')
NE cor. conc. block garage S 25° W 138.10' (m. 138.05')
Steel bar & cap N 90° E 6.62'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13 Standard Kent County Monument

Nail & K.C. remon. tag on N side cut P. pole S 67° W 95.25'
NE cor. conc. block garage S 25° W 138.05'
Nail & K.C. remon. tag on S side Tri 10" Ash N 55° E 78.67'
Nail & K.C. remon. tag on W side wood corner fence post N 00° E 26.77'
Steel bar and cap N 90° E 6.62'

Signed by Randy J. Kolehouse Date 10/8/96
EARTH TECH

Surveyor's Michigan License No. 25854

REG. OF DEEDS

Handwritten signature

96 NOV -8 AM 9:17

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

9453

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 2-13. A dot is marked at row 13, column A.

