

SURVEY & REMONUMENTATION

FEB 14 1997

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>5N</u> R <u>10W</u>	<u>D-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 6, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-1	1830	GLO	Not Set
	1971	Kent Co. Wit.	3/4" Iron
	1974	LCRC #742	Bonnema
	1984	LCRC #3819	Cettleburgh
	1994	LCRC #7077	Bueche

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96
CHAIRMAN Harry Huber
Witnesses

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas M. Chettleburgh on 4/30/84 and was recorded per LCRC #3819.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Thomas M. Chettleburgh on Twp. line 0.39' South of the Iron Pipe he found. Said Iron Pipe checks with LCRC #742.

LCRC #3819 & #7077

Nail & KC Remon. tag S. side 14" Maple	N72°E	73.00'
Nail & KC Remon. tag NW side 24" Maple	S02°W	28.78'
Nail & KC Remon. tag NW side 20" Maple	S68°W	67.43'
Nail & KC Remon. tag SW side 22" Maple	N54°E	44.23'
Kent Co. Mon. S 1/4, Sec. 32, 6-10	East	38.91'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 Standard Kent County Monument

Nail & KC Remon. tag S. side 14" dead Maple	N72°E	72.96'
Nail & KC Remon. tag NW side 24" dead Maple	S02°W	28.73'
Large Nail NW side 22" Maple	S68°W	67.50'
Large Nail SW side 26" Maple	N54°E	44.29'
Kent Co. Mon. S 1/4, Sec. 32, 6-10	East	38.93'



Signed by Kirk Breitels

Date 3/1/96

Surveyor's Michigan License No. 30077