

\$7.00  
\$2.00 SEP 18 1995

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	5N	R	10W	D-12
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Section	S	T	R		
	S	T	R		

REG. OF DEEDS

8531

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
95 JUL 11 PM 1:53

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Kirk Breitels, in a field survey on June 30, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-12 1830 GLO Not Set  
1972 LCRC #409 VanKooten "T" Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-12 Found "T" Iron per LCRC #409 and by previous surveys. Said "T" Iron is 0.1' N & 0.1' E. of true "X" 1/4 lines.

LCRC #409

Fence N 4.7' (ok m/l)  
Fence E-W S 0.7' (ok m/l)  
36" Maple SSW 168.43' (gone)  
20" Maple S 83.66' (gone)

P.A. 345 1990 KENT COUNTY

PEER APPROVED 6/22/95

CHAIRMAN Harry Hubers

The "T" Iron is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-12 Set Standard Kent County Monument in place of "T" Iron.

Set Nail & KC Remon. tag N. side 3" Cherry N80°E 4.59'  
Set Nail & KC Remon. tag W. side 3" Tree S15°E 3.07'  
Set Nail & KC Remon. tag S. side P. Pole N90°E 161.47'  
Set Nail & KC Remon. tag S. side P. Pole N90°W 348.62'  
Fence Post (leaning W'ly) for fence to North and East-West is West 5' m/l

Signed by Kirk Breitels

Date 7/6/95

30077

Surveyor's Michigan License No. \_\_\_\_\_

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS JAN 28 1975 REVISED MAY 14 1975

