

FEB 14 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Table with columns: Kent (County), Located in: Caledonia Township, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

STATE OF MICHIGAN COUNTY OF KENT RECEIVED FOR RECORD 96 NOV -8 AM 9:19 REG. OF DEEDS 9477 Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Randy Kolehouse, in a field survey on May 3 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with columns: E-2, 1831, G.L.O. Notes, Mullett, Set Post, 1964, Witness Map, K.C. Surveyor, Well Point, 1977, L.C.R.C. #1085, P. Van Kooten, Well Point, 1981, L.C.R.C. #2541, J. Bueche, Fnd. Well Point / Set K.C. Monument, 1987, L.C.R.C. #4556, Prein & Newhof, K.C. Monument, 1991, L.C.R.C. #5957, William Byl, K.C. Monument

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by J. Bueche on 12/23/81 and was recorded per L.C.R.C. #2541.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-2 Found a Standard Kent County Monument on line of a tree row running North and a tree row running East per L.C.R.C.'s #2541, #4556 and #5957 as set by J. Bueche in place of a well point he found which checked L.C.R.C. #1085 and the K.C. Surveyor's records.

L.C.R.C. #2541

L.C.R.C. #4556

L.C.R.C. #5957

Table with 3 columns corresponding to L.C.R.C. #2541, #4556, and #5957. Describes monument details like 'tag & nail in West side 4" Hickory N 30° E 1.90'', 'sq. spike in East side 12" W. Cherry N 30° E 26.66'', etc.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-2 Standard Kent County Monument

- Nail & K.C. remon. tag on W side 6" Hickory N 30° E 1.92'
Nail & K.C. remon. tag on SW side 6" W. Cherry N 30° W 38.13'
Nail & K.C. remon. tag on E side 12" W. Cherry N 30° E 26.72'
Nail & K.C. remon. tag on E side 12" Ash N 10° W 30.71'
Steel bar & cap (EXXEL) N 00° E 33.00'

Signed by Randy J. Kolehouse

Date 10/8/96



Surveyor's Michigan License No. 25854

P.A. 345 1990 KENT COUNTY, PEER APPROVED 7/25/96, CHAIRMAN [Signature]