

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in: Caledonia Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>10W</u>	<u>F-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

9616

Register of Deeds Stamp & File Number

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 96 DEC 27 AM 10:50

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Randy Kolehouse, in a field survey on April 9 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-4 This corner was not originally set by the G.L.O.

Date	Description	Surveyor	Material
1965	Witness Map	K.C. Surveyor	Stone
1927	Survey Notes	Williams & Works	Stone
1935	Survey Notes	Williams & Works	Stone
1972	L.C.R.C. #258	Exxel Engineering	Stone
1992	L.C.R.C. #6568	T. Chettleburgh	Fnd Stone / Set K.C. Monument

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 8/22/96
 CHAIRMAN [Signature]

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by T. Chettleburgh on 5/27/92 and was recorded per L.C.R.C. #6568.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-4 Found a Standard Kent County Monument per L.C.R.C. #6568 as set by T. Chettleburgh in place of a stone he found that checked L.C.R.C. #258 and Williams & Works' survey records from 1927 and 1935. Monument is 4.0' North and 2.0' East of the intersection of 1/4 lines. Accepted as the Center of Section.

L.C.R.C. #258

Nail in side 28" Oak SSE 17.02'
 Nail in side 20" Oak Wly 28.02'

L.C.R.C. #6568

Remon tag in NE side 21" Oak S 37° E 62.63'
 Remon tag in NE side 18" Oak S 03° E 16.94'
 Remon tag in E side 7" Tree (Oak) S 24° W 49.08'
 Remon tag in SE side 23" Oak N 85° W 27.80'
 Fence Corner Post S 77° W 3.68'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-4 Standard Kent County Monument

Nail & K.C. remon. tag on NE side 21" Oak S 37° E 62.63'
 Nail & K.C. remon. tag on NE side 18" Oak S 03° E 16.94'
 Nail & K.C. remon. tag on E side 7" Tree (Oak) S 24° W 49.08'
 Nail & K.C. remon. tag on SE side 23" Oak N 85° W 27.80'
 Fence corner post S 77° W 3.68'

Signed by [Signature]
 EARTH TECH

Date 12/24/96

Surveyor's Michigan License No. 25854

