

SURVEY & REMONUMENTATION

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

COMMISSION

Kent (County)	Located in: Caledonia Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>10W</u>	<u>H-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

Lucy Stand

96 NOV -8 AM 9:22

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD

9519

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Randy Kolehouse, in a field survey on March 29 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-12 This corner was not originally set by the G.L.O.

1947	Witness Map	K.C. Surveyor	2" Iron
1984	L.C.R.C. #528	Exxel Engineering	2" Iron

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 8/22/96
 CHAIRMAN *Harry Huber*

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	●	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-12 Found a 1/2" capped rebar on the C/L of Alaska Avenue running North and South on line of power lines running East and West per L.C.R.C. #528 and the K.C. Surveyor's records. Capped rebar is 9.9' East and 2.4' North of the intersection of 1/4 lines. Accepted rebar as Center of Section.

L.C.R.C. #528

Nail in side P. Pole W 59.41'
 C/L conc. post E 29.0'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-12 Replaced 1/2" Capped Rebar with a Standard Kent County Monument

- Nail & K.C. remon. tag on W side P. pole N 15° W 112.85'
- Nail & K.C. remon. tag on S side P. pole S 85° W 59.35'
- Nail & K.C. remon. tag on NW side 28" Willow N 35° E 70.12'
- C/L concrete R.O.W. N 85° E 29.0'

Signed by *Randy J Kolehouse*

EARTH TECH

Date 10/8/96

Surveyor's Michigan License No. 25854

