

**SURVEY & REMONUMENTATION**

~~\$7.00~~  
\$2.00

FEB 14 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

For corners in

| Kent<br>(County)                      | Located in: | Caledonia<br>Township | Corner Code # |
|---------------------------------------|-------------|-----------------------|---------------|
| 1. Public Land Survey                 | T <u>5N</u> | R <u>10W</u>          | <u>H-13</u>   |
|                                       | T _____     | R _____               | _____         |
|                                       | T _____     | R _____               | _____         |
|                                       | T _____     | R _____               | _____         |
| 2. Property Controlling<br>in Section | S _____     | T _____               | R _____       |
|                                       | S _____     | T _____               | R _____       |
| 3. Miscellaneous<br>Property in Sec.  | S _____     | T _____               | R _____       |
|                                       | S _____     | T _____               | R _____       |

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
96 NOV -8 AM 9:22  
REG. OF DEEDS  
*Lucy Bond*  
**9520**  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 16 |   | 17 |   | 18 |   | 19 |   | 20 |   | 21 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

I, Randy Kolehouse, in a field survey on April 5 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

|      |      |                |                     |  |
|------|------|----------------|---------------------|--|
| H-13 | 1817 | G.L.O. Notes   | L. Lyon             | Set Post                                 |
|      | N/A  | Witness Map    | K.C. Surveyor       | Boat Spike                               |
|      | 1983 | L.C.R.C. #3219 | Exxel Engineering   | 3/4" Iron                                |
|      | 1983 | L.C.R.C. #3694 | Jonker Land Surveys | Fnd. 3/4" Round Iron / Set K.C. Monument |
|      | 1995 | L.C.R.C. #8111 | K. Breitels         | K.C. Monument                            |

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 7/25/96  
CHAIRMAN Randy Kolehouse

This corner is not common with H-1, T4N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Rob Jonker on 4/6/83 and was recorded per L.C.R.C. #3694.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 Found a Standard Kent County Monument in the C/L intersection of 108th Street (bit.) running East and West and Alaska Avenue (gravel) running North per L.C.R.C.'s #3694 and #8111 as set by Rob Jonker in place of a 3/4" round iron he found which checked L.C.R.C. #3219 and the K.C. Surveyor's records.

L.C.R.C. #3694

L.C.R.C. #8111

Remon. tag on NE side p. pole N 30° W 47.12'  
Remon. tag on W side p. pole N 40° E 59.30'  
Remon. tag on SW side p. pole S 55° E 73.52'  
Capped Iron East 44.43'  
C/L E-W B.T. South 3'  
C/L Gravel to Nail & tag, East 12' m/l

Nail & KC Remon. tag NE side P. Pole N 30° W 47.12'  
Nail & KC Remon. tag W. side P. Pole N 40° E 59.15'  
Nail & KC Remon. tag NE side P. Pole S 55° E 73.80' (m. 73.74')  
Capped Iron S 90° E 44.43'  
C/L E-W B.T. South 3'; C/L Gravel to N. is East 12' m/l

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 Standard Kent County Monument

Nail & K.C. remon. tag on NE side P. pole N 30° W 47.12'  
Nail & K.C. remon. tag on NW side P. pole N 40° E 59.15'  
Nail & K.C. remon. tag on NE side P. pole S 55° E 73.74'  
Nail & K.C. remon. tag on E side 6" Elm S 20° W 49.72'  
Capped Iron N 90° E 44.50'

Signed by Randy J. Kolehouse Date 10/8/96

Surveyor's Michigan License No. 25854

