

SURVEY & REMONUMENTATION

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent **COMMISSION**
 (County)

Located in: Caledonia
 Township

Corner Code #

- 1. Public Land Survey T 5N R 10W I-12
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Randy Kolehouse, in a field survey on May 1 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-12	1831	G.L.O. Notes	Mullett	Set Post
	1966	Witness Map	K.C. Surveyor	Large Pointed Stone
	1973	L.C.R.C. #528	Exxel Engineering	Pointed Stone with "X" on Top
	1980	L.C.R.C. #1478	Williams & Works	Fnd. Pointed Stone with "X" Cut / Set K.C. Monument
	1995	L.C.R.C. #8122	K. Breitels	K.C. Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 8/22/96

CHAIRMAN Randy Kolehouse

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 11/25/80 and was recorded per L.C.R.C. #1478.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-12 Found a Standard Kent County Monument 49' ± South of power lines running East and West on line of fence row running East and West per L.C.R.C.'s #1478 and #8122 as set by Williams & Works in place of a pointed stone they found with an "X" cut which checked L.C.R.C. #528 and the K.C. Surveyor's records.

L.C.R.C. #1478

L.C.R.C. #8122

- K.C.R. Tag & Nail in W Side 16" Beech S 30° E 26.23'
- K.C.R. Tag & Nail in E Side 22" Beech S 00° E 39.32'
- K.C.R. Tag & Nail in SE Side 22" Beech S 40° W 37.53'
- K.C.R. Tag & Nail in N Side 24" Beech S 70° W 61.13'
- K.C.R. Tag & Nail in E Side 14" Ash N 00° E 117.55'

- KC Remon. tag & Nail W. side 20" Beech S 30° E 26.25'
- KC Remon. tag & Nail E. side 28" Beech S 00° E 39.35'
- KC Remon. tag & Nail SE side 26" Beech S 40° W 37.52'
- KC Remon. tag & Nail N. side 24" Beech S 70° W 61.24'
- KC Remon. tag & Nail E. side 20" Ash N 00° E 117.57'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12 Standard Kent County Monument

- Nail & K.C. remon. tag on W side 20" Beech S 30° E 26.25'
- Nail & K.C. remon. tag on E side 28" Beech S 00° E 39.35'
- Nail & K.C. remon. tag on SE side 26" Beech S 40° W 37.52'
- Nail & K.C. remon. tag on N side 24" Beech S 70° W 61.24'
- Nail & K.C. remon. tag on E side 20" Ash N 00° E 117.57'

Signed by Randy J. Kolehouse

Date 10/8/96

EARTH TECH

Surveyor's Michigan License No. 25854

