

**SURVEY & REMONUMENTATION**

FEB 14 1997

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

**COMMISSION**

KENT COUNTY REMONUMENTATION

For corners in

Kent  
(County)

Located in: Caledonia  
Township

Corner Code #

1. Public Land Survey	T	<u>5N</u>	R	<u>10W</u>	<u>J-4</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous Property in Sec.	S		T		
	S		T		

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on April 9 19 96, do hereby certify that under requirements of P.A. 74 Michigan, P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

J-4 This corner was not originally set by the G.L.O.

1963	Witness Map	K.C. Surveyor	"X" in Pavement
1975	L.C.R.C. #900	Williams & Works	Boat Spike
1993	L.C.R.C. #6723	T. Chettleburgh	Fnd. Boat Spike / Set K.C. Monument
1995	L.C.R.C. #8125	K. Breitels	K.C. Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 8/22/96  
CHAIRMAN [Signature]

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by T. Chettleburgh on 1/16/93 and was recorded per L.C.R.C. #6723

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-4 Found a Standard Kent County monument 1' ± West of the C/L of Whitneyville Road (bit.) running North and South on line of tree row running West per L.C.R.C.'s #6723 and #8125 as set by T. Chettleburgh in place of a boat spike he found that checked L.C.R.C. #900. Kent County monument is 0.07' East and 0.04' South of the intersection of 1/4 lines.

L.C.R.C. #6723

Nail/Tag NW side 11" Hickory N 59° E 31.83'  
Nail/Tag W side 11" Hickory S 20° E 69.96'  
Nail/Tag N side 9" Maple S 85° E 38.64'  
E. Face of Sq. 10"X10" Con. Post N 87° W 33.31'  
Iron pipe in Monument Box S 03° E 6.14'

L.C.R.C. #8125

Nail & KC Remon. tag NW side 15" Hickory N 59° E 31.90'  
Nail & KC Remon. tag W. side 11" Hickory S 20° E 69.99'  
PK Nail & KC Remon. tag side P. Pole S 55° E 74.88'  
E. face of Sq. 10" x 10" Conc. Post N 87° W 33.31'  
Iron Pipe in mon. box N 87° W 33.31'  
"T" Iron - West 32.75'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-4 Standard Kent County Monument

Nail & K.C. remon. tag on NW side 15" Hickory N 59° E 31.90'  
Nail & K.C. remon. tag on W side 11" Hickory S 20° E 69.99'  
Nail & K.C. remon. tag on side P. pole S 55° E 74.88'  
E face of sq. 10" x 10" conc. post N 87° W 33.31'  
Iron pipe in mon. box N 87° W 33.31'  
"T" iron - West 32.75'

Signed by [Signature] Date 12/24/96  
EARTH TECH  
Surveyor's Michigan License No. 25854

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
96 DEC 27 AM 10:50  
REG. OF DEEDS  
[Signature]  
**9617**  
Register of Deeds Stamp & File Number

