

57.00 REMONUMENTATION
12.00

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in COMMISSION
Kent
(County)

Located in: Caledonia Township
Corner Code #

- | | | | |
|------------------------------------|-------------|--------------|-------------|
| 1. Public Land Survey | T <u>5N</u> | R <u>10W</u> | <u>J-13</u> |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

96 NOV -8 AM 9:23

REG. OF DEEDS
W. J. [Signature]

9545

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on April 5 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-13 1817	G.L.O. Notes	L. Lyon	Set Post
1939	Witness Map	K.C. Surveyor.	Monument
1976	L.C.R.C. #954	Exxel Engineering	1" Iron
1984	L.C.R.C. #3840	R. Kolehouse	Fnd. 1" Iron / Set K.C. Monument
1995	L.C.R.C. #8130	K. Breitels	K.C. Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 8/22/96
CHAIRMAN [Signature]

Note: This corner is not common with J-1, T4N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 4/7/84 and was recorded per L.C.R.C. #3840.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13 Found a Standard Kent County Monument 52' South of the C/L of 108th Street running East and West on line of a chain link fence running West per L.C.R.C.'s #3840 and #8130 as set by Randy Kolehouse in place of a 1" iron he found 52' South of the C/L of 108th Street which checked L.C.R.C. #954 and the K.C. Surveyor's records.

L.C.R.C. #3840

- Nail & K.C. Remon. tag in E. side 30" Ash S 15° E 19.22'
- Nail & K.C. Remon. tag in E. side 12" Ash S 30° W 24.66'
- Nail & K.C. Remon. tag in SE side P. Pole S 60° W 73.43'
- SW corner conc. wingwall N 60° E 63.55'
- E. face steel fe. post West 0.63'
- C/L 108th Street blacktop North 52' m/l


L.C.R.C. #8130

- Nail & KC Remon. tag E. side 40" Ash S 15° E 19.16' (m. 19.11')
- Nail & KC Remon. tag E. side 18" Ash S 30° W 24.72' (m. 24.61')
- Nail & KC Remon. tag SE side P. Pole S 60° W 73.43' (m. 73.41')
- SW corner conc. wingwall N 60° E 63.55'
- E. face of steel fence post West 0.63'
- C/L 108th St. blacktop - North 52' m/l

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-13 Standard Kent County Monument
- Nail & K.C. remon. tag on E. side 40" Ash S 15° E 19.11'
 - Nail & K.C. remon. tag on E side 18" Ash S 30° W 24.61'
 - Nail & K.C. remon. tag on SE side P. pole S 60° W 73.41'
 - SW corner wingwall N 60° E 63.55'
 - E face steel fence post West 0.63'



Signed by Randy J. Kolehouse
EARTH TECH

Date 10/8/96

Surveyor's Michigan License No. 25854