

Survey & Remonumentation

\$7.00
\$2.00

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

KENT COUNTY REMONUMENTATION

Kent (County)	Located in:	Caledonia Township	Corner Code #
1. Public Land Survey	T <u>5N</u>	R <u>10W</u>	<u>K-13</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 NOV -8 AM 9:24
REG. OF DEEDS
W. J. Cole
9562

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on April 10 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-13	1817	G.L.O. Notes	L. Lyon	Set Post	P.A. 345 1990 KENT COUNTY
	1939	Witness Map	K.C. Surveyor	Monument	PEER APPROVED <i>7/29/96</i>
	1973	L.C.R.C. #410	Medema, Van Kooten & Assoc.	Monument	CHAIRMAN <i>Randy Kolehouse</i>
	1981	L.C.R.C. #1710	Williams & Works	Fnd. Concrete Monument / Set K.C. Monument	

Note: This corner is not common with K-1, T4N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 2/20/81 and was recorded per L.C.R.C. #1710.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 Found a Standard Kent County Monument 30' W of C/L of Winding River Road running North per L.C.R.C.'s #1710 as set by Williams & Works in place of concrete monument they found which checked L.C.R.C. #410 and the K.C. Surveyor's records.

L.C.R.C. #1710

Nail & K.C. Remon. Tag in W. Side 26" Oak S 15° W 52.18'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 Standard Kent County Monument

- Nail & K.C. remon. tag on W side 12" Maple N 05° E 63.80'
- Nail & K.C. remon. tag on W side 24" Oak S 15° W 52.07'
- Nail & K.C. remon. tag on NW side 24" Oak S 72° E 198.37'
- Nail & K.C. remon. tag on SW side 16" Oak N 78° W 209.74'

Signed by *Randy J. Kolehouse*
EARTH TECH

Date 10/8/96

Surveyor's Michigan License No. 25854

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

