

2/10
 SURVEY &
 REMONUMENTATION

FEB 14 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 KENT COUNTY REMONUMENTATION

For corners in

For corners in	Located in:	Caledonia Township	Corner Code #
<u>Kent</u> (County)			
1. Public Land Survey	T <u>5N</u>	R <u>10W</u>	<u>L-12</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 96 DEC 20 PM 12:42
 REG. OF DEEDS
Luis J. Bond

9613

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on August 21 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-12 This corner was not originally set by the G.L.O.

Found no additional information on record. Also checked Kent County Surveyor's witness map and found no information pertaining to this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-12 Found fence post loose in swamp 10' South of the C/L of power lines running East and West. Decided to set Center at the intersection of 1/4 lines. Fence post is 0.2' West of the Center Section as set.

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 10/24/96
 CHAIRMAN *Randy Kolehouse*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-12 Set a Standard Kent County Monument:

- Nail & K.C. remon. tag on W side: 10" Ash N 01° W 61.33'
- Nail & K.C. remon. tag on NW side 10" Maple N 35° E 72.72'
- Nail & K.C. remon. tag on E side 6" Ash S 28° E 24.65'
- Nail & K.C. remon. tag on SW side Util. pole over old PK nail N 83° W 117.05'
- On line m/l with old wire fence remnants running North, strung on trees
- NE cor. conc. fndn. garage S 70° E 52.36'
- Corner is 10' ± South of overhead lines

Signed by Randy J. Kolehouse Date 12/9/96

EARTH TECH

Surveyor's Michigan License No. 25854

