

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

other code #13

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
96 DEC 27 AM 10:49
REG. OF DEEDS

For corners in

COMMISSION

Table with columns: Kent (County), Located in: Caledonia Township, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

9614

Register of Deeds Stamp & File Number

- 4. Lot No.
5. Private Claims

I, Randy Kolehouse, in a field survey on October 29 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-10 This corner was not originally set by the G.L.O.

Table with columns: Year, Survey Notes, Williams & Works, 3/4" Iron. Rows: 1947 Survey Notes Williams & Works 3/4" Iron; 1973 L.C.R.C. #373 Williams & Works 3/4" Iron

P.A. 345 1990 KENT COUNTY
PEER APPROVED 10/24/96
CHAIRMAN [Signature]

Grid table with columns A-L and rows 1-12. A dot is marked at the intersection of column C and row 10.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-10 The 3/4" iron and all witnesses shown in L.C.R.C. #373 have been destroyed. This corner now falls within a building (Lakeview Villa Condominiums). Reestablished 1/4 lines using survey information from Williams & Works (1947). Checks this information +/- 0.10'. Computed location for the Center of Section is 3.4' North and 1.5' West of the intersection of 1/4 lines. Set a reference monument 1341.60' East of D-10 using Williams & Works' survey records.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-10 Set Standard Kent County Reference Monument

- SE corner brick pillar at SE porch corner N 47° E 61.92'
Inside corner conc. sidewalk S 41° E 45.30'
NW corner stone fndn. House #131 S 54° W 91.98'
SW corner conc. fndn. House #401 N 46° W 84.05'

Signed by Randy J. Kolehouse
EARTH TECH

Date 12/24/96

Surveyor's Michigan License No. 25854

