

FEB 14 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Table with columns: Kent (County), Located in: Gaines Township, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

STATE OF MICHIGAN COUNTY OF KENT RECEIVED FOR RECORD 95 AUG -8 AM 8:37 REG. OF DEEDS 9206 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Randy Kolehouse, in a field survey on January 5, 1996, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-6 This corner was not originally set by the G.L.O.
1969 Witness Map K.C. Surveyor 3/4" Iron
1976 L.C.R.C. #931 Exxel Engineering "T" Iron
1983 L.C.R.C. #3516 William Byl Fnd. Exxel Iron / Set K.C. Monument
1991 L.C.R.C. #6430 Chris Marschall Kent County Monument

Note: This corner is not common with M6, T5N, R12W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 9/27/83 and was recorded per L.C.R.C. #3516.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6 Found a Standard Kent County Monument 95' M/L West of the center line of Division Avenue running N-S and 20' M/L North of a fence line running E-W as set by William Byl in place of a capped Exxel iron he found which checked L.C.R.C. #931 and the Kent County Surveyor's records as being 19.51' North of M-6, T5N, R12W.

L.C.R.C. #3516

L.C.R.C. #6430

SE cor. bldg. #7985, 1' above grd. N 60 E 19.32'
South face of bldg. foundation N 00 E 11.31'
NW cor. foundation, Hse. # 8007 S 15 W 35.77'
NE cor. foundation, Hse. # 8007 S 25 E 40.37'
East 1/4 cor. Sec. 13, 5-12 (Kent County Monument)

SE cor Bldg. #7985 (1' above grd) N 60 E 19.33'
South face of Bldg. Fndn. N 00 E 11.31'
NW cor of siding Hse #8007 "siding" S 15 W 35.53'
NE cor of siding Hse #8007 "siding" S 25 E 40.28'
East 1/4 cor Sec. 13 5-12 (Kent County Monument S 00 W 19.51'
Centerline Division Ave. West more or less 95'
Corner located at the bottom of the Bank

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6 Standard Kent County Monument
SE cor. bldg. #7985 1' above ground N 60° E 19.33'
S face of bldg. fndn. N 00° E 11.31'
NE cor. siding hse. #8007 S 25° E 40.28'
NW cor. siding hse. #8007 S 15° W 35.53'
K.C. Mon. E 1/4 13, T5N, R12W, S 00° W 19.51'

Signed by Randy J. Kolehouse Date 7/23/96

Surveyor's Michigan License No. 25854

Grid table with columns A-L and rows 1-13. Cell 6,6 is circled.

P.A. 345 1990 KENT COUNTY PEER APPROVED 3/7/96 CHAIRMAN Randy Hubel

