

SURVEY & REMONUMENTATION

FEB 14 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent
 (County)

Located in: Gaines
 Township

Corner Code #

1. Public Land Survey	T <u>5N</u>	R <u>11W</u>	<u>A-7</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

REG. OF DEEDS

Handwritten signature

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 95 AUG -8 AM 8:37

9207

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Randy Kolehouse, in a field survey on January 5 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-7	1831	G.L.O. Notes	Mullett	Set Post
	1973	Witness Map	K.C. Surveyor	Monument Box
	1973	L.C.R.C. #641	Exxel Engineering	1" Solid Iron
	1983	L.C.R.C. #3517	William Byl	Fnd. 1" Iron / Set K.C. Monument
	1991	L.C.R.C. #6421	Chris Marschall	K.C. Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96

CHAIRMAN *Handwritten signature*

Note: This corner is not common with M-7, T5N, R12W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 9/26/83 and was recorded per L.C.R.C. #3517.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7 Found a Standard Kent County Monument at the C/L intersection of Division Avenue and 84th Street (bit.) 14.51' North of M-7, T5N, R12W (monument is on the Township line) as set by William Byl along side a 1" solid iron he found to be 0.28' West of the Town line that checked L.C.R.C. #641. K.C. Monument checks L.C.R.C.'s #3517 and #6421.

L.C.R.C. #3517

L.C.R.C. #6421

Nail & tag, E sd. guy pole S 40 W 70.39'
 Nail & tag, S sd. Power pole N 55 E 65.83'
 NW corner of House # 7, 5' above ground S 35 E 159.58'
 NE cor. Sec. 24, 5-12, (Kent County Monument) S 00 W 14.51'

"X" in top of conc. R.O.W. Marker N 23 E 126.68'
 "X" in top of conc. R.O.W. Marker S 50 E 66.96' (m. 66.95')
 SE cor. Sec. 13, 5N, 12W S 00 W 14.54' (m. 14.53')
 Nail & Tag SE Sd Guy Pole N 45 E 65.80'
 Nail & Tag SE Sd U.P. S 45 W 70.29'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7 Standard Kent County Monument on the Township Line

"X" in top R.O.W. marker N 23° E 126.68'
 Nail & K.C. remon. tag on SE side Guy pole N 45° E 65.80'
 "X" in top R.O.W. marker S 50° E 66.96'
 NW cor. hse. 5' high S 35° E 159.49'

Nail & K.C. remon. tag on SE side P. pole S 45° W 70.29'
 Nail & K.C. remon. tag on W side P. pole N 45° W 48.34'
 K.C. Mon. SE 13, T5N, R12W, S 00° W 14.53'

Signed by Randy J. Kolehouse

Date 7/23/96

EARTH TECH

Surveyor's Michigan License No. 25854

