

**SURVEY & REMONUMENTATION**

FEB 14 1997

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**KENT COUNTY REMONUMENTATION**

For corners in

Kent (County)	Located in: Gaines Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>A-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 96 AUG -8 AM 8:38  
 REG. OF DEEDS  
*Eric J. Standt*

**9208**  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Randy Kolehouse, in a field survey on January 5 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

A-8	This corner was not originally set by the G.L.O.				P.A. 345 1990 KENT COUNTY
	1906-1957	Survey Records	Williams & Works	Iron	PEER APPROVED <u>3/17/96</u>
	1964	Witness Map	K.C. Surveyor	Iron	CHAIRMAN <i>Hannif Thurber</i>
	1983	L.C.R.C. #3575	William Byl	Found Iron / Set K.C. Monument	
	1991	L.C.R.C. #6422	Chris Marschall	K.C. Monument	

Note: This corner is not common with M-8, T5N, R12W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 9/27/83 and was recorded per L.C.R.C. #3575.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

A-8 Found a Standard Kent County Monument per L.C.R.C.'s #3575 and #6422 1.93' North of M-7, T5N, R12W, as set by William Byl in place of a 1" x 18" iron pipe he found which checked Williams & Works' survey records as well as the K.C. Surveyor's records.

**L.C.R.C. #3575**

Nail & tag, N sd. 15" Beech S 70 W 40.03'  
 Nail & tag, N sd. 24" Maple S 85 E 29.45'  
 E 1/4 cor. Sec. 24, 5-12, (Kent County Monumet) S 00 W 1.93'

**L.C.R.C. #6422**


Nail & Tag E sd. Twin 16" Maple S 19 W 52.82'  
 Nail & Tag N sd. 16" Beech S 68 W 40.08'  
 Nail & Tag NE sd. 12" Maple N 48 W 27.85'  
 Nail & Tag S sd. 24" Maple S 83 E 29.46'  
 E 1/4 cor. Sec. 24 T5N, R12W S 00 E 1.93'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A-8 Standard Kent County Monument on the Town Line

- Nail & K.C. remon. tag on Twin 16" Maple S 19° W 52.82'
- Nail & K.C. remon. tag on N side 16" Beech S 68° W 40.08'
- Nail & K.C. remon. tag on NE side 12" Maple N 48° W 27.85'
- Nail & K.C. remon. tag on S side 24" Maple S 83° E 29.46'
- E 1/4 24, T5N, R12W, (K.C. Mon.) S 00° E 1.93'



Signed by *Randy J. Kolehouse* Date 7/23/96  
 EARTH TECH

Surveyor's Michigan License No. 25854