

SURVEY & REMONUMENTATION

FEB 14 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Gaines Township	Corner Code #
1. Public Land Survey	T <u>5N</u>	R <u>11W</u>	<u>A-13</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 96 AUG -8 AM 8:38
 REG. OF DEEDS
[Signature]

9213

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Randy Kolehouse, in a field survey on January 5 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-13	1817	G.L.O. Notes	L. Lyon	Set Post
	1954	Survey Notes	Williams & Works	Iron Rod
	1956	Wit. Map	K.C. Surveyor	Leaded Stone
	1981	L.C.R.C. #1816	Exxel Engineering	Found 5/8" Rod on C/L Set K.C. Monument
	1992	L.C.R.C. #6373	Chris Marschall	K.C. Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96
 CHAIRMAN *[Signature]*

Note: This corner is common with M-13, T5N, R12W; M-1, T4N, R12W; and A-1, T4N, R11W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Exxel Engineering on 5/4/81 and was recorded per L.C.R.C. #1816.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13 Found standard Kent County Monument on the C/L of Division Street running N-S per L.C.R.C.'s #1816 and #6373 as set by Exxel Engineering in place of 5/8" rod on C/L they found which checked Williams & Works' Survey Notes - 1954 - and K.C.R.C. Wit. Map.

L.C.R.C. #1816

L.C.R.C. #6373

PK in top of W'ly end of drive culvert S58°W 38.30'
 Nail & KC tag in E sde 8" Ash N18°W 148.46'
 Nail & KC tag in E sde 8" Ash S30°W 96.96'


PK Nail in top of Westerly end of drive culvert S 58 W 38.32'
 Nail & Tag E sd. 10' Ash (4' above ground) N 19 W 148.17'
 Nail & Tag SW sd. P.P. N 63 W 99.02'
 Nail & Tag E sd 12" Ash S 30 W 96.90'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13 Standard Kent County Monument

P.K. nail in top W'ly end of drive culvert S 60° W 38.31'
 Nail & K.C. remon. tag on E side 10" Ash (4' above ground) N 20° W 148.19'
 Nail & K.C. remon. tag on SW side P. pole N 63° W 99.01'
 Nail & K.C. remon. tag on E side 12" Ash S 30° W 96.97'
 Nail & K.C. remon. tag on S side P. pole N 90° E 133.50'
 W'ly of NW cor. metal frame office Bldg. #4799 S 62° E 131.14'



Signed by *[Signature]* Date 7/23/96

Surveyor's Michigan License No. 25854