

**SURVEY & REMONUMENTATION**

FEB 14 1997

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**KENT COUNTY REMONUMENTATION**

For corners in

Kent (County)	Located in: Gains Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>B-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

9219

Register of Deeds Stamp & File Number

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 96 AUG -8 AM 8:38

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Randy Kolehouse, in a field survey on January 25 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

B-11	1831	G.L.O. Notes	Mullett	Set Post
	1956	Witness Map	K.C. Surveyor	Iron in Monument Box
	1973	L.C.R.C. #526	Exxel Engineering	Iron in Monument Box
	1982	L.C.R.C. #3071	Jonker Land Survey	Fnd. 3/4" Iron in Mon. Box / Set K.C. Monument
	1989	L.C.R.C. #5013	J. Bueche	K.C. Monument in Mon. Box

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Jonker Land Survey on 8/5/82 and was recorded per L.C.R.C. #3071.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-11 Found a Standard Kent County Monument in a monument box on the C/L of 100th Street (bit.) running East and West and on line of a tree row running North per L.C.R.C.'s #3071 and #5013 as set by Rob Jonker in place of a 3/4" iron he found in a monument box which checked K.C. Surveyor's records.

L.C.R.C. #3071

L.C.R.C. #5013

Remon. tag on E side 34" Maple North 38.58'  
 NE corner brick house S 45° E 111.06'  
 NW corner brick house S 10° E 87.20'  
 NE corner brick house S 45° W 150.5'

Nail & Remon Tag on E side 38" Maple North 38.58'  
 NE corner brick house S 45° E 111.06' (m. 110.83')  
 NW corner brick house S 10° E 87.20' (m. 87.08')  
 NE corner brick house S 45° W 150.5' (m. 150.31')  
 On C/L E-W pavt.  
 On tree line to N & S

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11 Standard Kent County Monument in a Monument Box

NE corner brick house S 45° E 110.83'  
 NW corner brick garage S 10° E 87.08'  
 NE corner brick house S 45° W 150.31'  
 Nail & K.C. remon. tag on E side 38" Maple N 00° E 38.58'



Signed by Randy J. Kolehouse Date 7/23/96

Surveyor's Michigan License No. 25854