

JAN 23 1996

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 KENT COUNTY REMONUMENTATION

For corners in **COMMISSION**

<u>Kent</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>B-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 95 DEC 28 PM 2:23
 REG. OF DEEDS
Lucy Bond
 8927
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Randy Kolehouse, In a field survey on November 10 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-12 This corner was not originally set by the G.L.O.

1961	Survey Records	Williams & Works	Set "T" Iron at Intersection of 1/4 Lines
1973	L.C.R.C. #526	Exxel Engineering	Reset "T" Iron Per Williams & Works Notes

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-12 Found "T" iron per L.C.R.C. #526 1.5' below ground surface. All witnesses have been destroyed.

Check dist. to W 1/4 - Meas. 2,501.93' Exxel = 2,501.88'
 Check dist. to E 1/4 - Meas. 2,654.96' Exxel = 2,654.98'

Accepted "T" iron as Center Section. Corner is cultivated field.

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 9/28/95
 CHAIRMAN *Harry Huber*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-12 Set a standard 4" x 30" Kent County Monument.

Kent County Monument at A-12 West 2,501.93'
 Kent County Monument at B-11 North 2,656.33'
 Kent County Monument at C-12 East 2,654.96'
 Kent County Monument at B-13 South 2,656.11'
 Iron stake near NW corner barn S 80° E 2,259.53'

No other witnesses available as corner falls in center of cultivated field.

Signed by *Randy J. Kolehouse* Date 12/27/95
 EARTH TECH

Surveyor's Michigan License No. 25854

