

**SURVEY & REMONUMENTATION**

FEB 14 1997

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**KENT COUNTY REMONUMENTATION**

For corners in

Kent (County)	Located in:	Gaines Township	Corner Code #
1. Public Land Survey	T <u>5N</u>	R <u>11W</u>	<u>B-13</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

96 AUG -8 AM 8:38

REG. OF DEEDS  
*Lucy Bond*  
**9220**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on January 29 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

B-13	1817	G.L.O. Notes	L. Lyon	Set Post
	1974	Survey Notes	Consumers Power Co.	"T" Iron
	1983	L.C.R.C. #3389	William Byl	Set K.C. Monument
	1989	L.C.R.C. #5014	J. Bueche	K.C. Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 6/17/96  
CHAIRMAN *Randy Kolehouse*

Note: This corner is not common with B-1, T4N, R11W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 4/20/83 and was recorded per L.C.R.C. #3389.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

B-13 Found a Standard Kent County Monument per L.C.R.C.'s #3389 and #5014 as set by William Byl per Consumers Power Company survey records.

L.C.R.C. #3389	L.C.R.C. #5014
Placed several 6" stones around monument	6" dia. wood post 5' high South 0.86' Iron N 1/4 cor. Sec. 6, 4-11 West 51.41' Field division E-W and North

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

B-13 Standard Kent County Monument

Nail & K.C. remon. tag on W side W.T. post South 0.86'  
Iron N 1/4 Sec. 6, T4N R11W West 54.41'  
K.C. Mon. at A-13 - West 2481.22'  
K.C. Mon. at B-12 - North 2656.11'



Signed by *Randy J. Kolehouse*  
EARTH TECH

Date 7/23/96

Surveyor's Michigan License No. 25854

