

SURVEY & REMONUMENTATION

FEB 14 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Gaines Township	Corner Code #
1. Public Land Survey	T <u>5N</u>	R <u>11W</u>	<u>C-6</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

REG. OF DEEDS

Lucy Standa

96 AUG -8 AM 8:39

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD

9226

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on January 22 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-6	1831	G.L.O. Notes	Mullett	Set Post
	1963	Witness Map	K.C. Surveyor	Iron & Stone
	1974	L.C.R.C. #683	Exxel Engineering	"Bolt" Spike
	1982	L.C.R.C. #2929	Exxel Engineering	Fnd. "Bolt" Spike in a 3" x 30" Pipe / Set K.C. Monument
	1989	L.C.R.C. #5019	J. Bueche	K.C. Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96

CHAIRMAN Randy Kolehouse

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Exxel Engineering on 5/3/982 and was recorded per L.C.R.C. #2929.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-6 Found a Standard Kent County Monument 0.5' West of the C/L of Eastern Avenue (bit.) running N-S on line of a fence running West per L.C.R.C.'s #2929 and #5019 as set by Exxel Engineering in place of a boat spike in a 3" x 30" iron they found which checked L.C.R.C. #683.

L.C.R.C. #683

L.C.R.C. #2929

L.C.R.C. #5019

Nail in sde P. Pole E 128.13'	Nail & KC tag in S sde P. Pole West 108.00'	Nail & Remon tag in S side p. pole West 108.00'
Nail in sde Fe Post W 50.53'	Nail & KC tag in E sde MBT pole N 5° W 248.63'	Nail & Remon Tag in E side MBT pole N 5° W 248.63'
C/L Pvt. East 0.5'	Nail & KC tag in S sde P. Pole East 128.24'	Nail & Remon Tag in S side p. pole East 128.24'
	C/L blacktop pavement East 0.5'	C/L blacktop West, East 0.5'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6 Standard Kent County Monument

- Nail & K.C. remon. tag on E side P. pole N 05° W 248.63'
- Nail & K.C. remon. tag on S side P. Pole East 182.24'
- Nail & K.C. remon. tag on W side 12" Elm S 40° W 110.65'
- Nail & K.C. remon. tag on S side P. pole West 108.00'
- Nail & K.C. remon. tag on N side 12" Maple N 60° W 76.36'

Signed by Randy J Kolehouse

EARTH TECH

Date 7/23/96

Surveyor's Michigan License No. 25854

