

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
COMMISSION

KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Gaines Township	Corner Code #
1 Public Land Survey	T <u>5N</u>	R <u>11W</u>	<u>C-8</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2 Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3 Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
96 AUG -8 AM 8:39  
REG. OF DEEDS  
*Lucy Spaul*

9228

Register of Deeds Stamp & File Number

4 Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5 Private Claims \_\_\_\_\_

Randy Kolehouse, in a field survey on January 22 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A Description of original monument and accessories and/or subsequent restoration:

C-8	1831	G.L.O. Notes	Mullett	Set Post
	1962	Witness Map	K.C. Surveyor	"T" Iron
	1972	L.C.R.C. #236	F.E. Spicer	1" Iron Pipe
	1977	L.C.R.C. #1058	Exxel Engineering	1" Iron Pipe
	1982	L.C.R.C. #2912	Exxel Engineering	Fnd. 1" Iron Pipe & "T" Iron Below Surface / Set K.C. Monument
	1989	L.C.R.C. #5021	J. Bueche	K.C. Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96

CHAIRMAN *Fanny Stuber*

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Exxel Engineering on 6/1/82 and was recorded per L.C.R.C. #2912.

B Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-8 Found a Standard Kent County Monument 5.6' East of the C/L of Eastern Avenue (bit.) running North and South per L.C.R.C.'s #2912 and #5021 as set by Exxel Engineering in place of 1" iron pipe over a "T" iron they found which checked L.C.R.C.'s #1058, 236 and K.C. Surveyor's records.

L.C.R.C. #2912

L.C.R.C. #5021

Nail & tag in N sde 24" Basswood S 66° W 56.65'  
NE cor gar N 45° W 171.32'  
PK & tag in top wooden guard rail post N 80° E 9.38'  
PK & tag in top wooden guard rail post S 14° E 38.82'  
Nail & tag in SW sde 14" Maple S 18° E 93.25'  
Nail & tag in E'ly sde P. pole N 33° E 123.55'  
C/L b.t. road West 5.6'

Nail & Remon Tag in N side 28" Basswood S 66° W 56.65' (m. 56.60')  
NE corner gar N 45° W 171.32' (m. 171.20')  
Nail & Remon Tag in top wooden guard rail post N 90° E 10.35' (m. 10.65')  
Nail & Remon Tag in top wooden guard rail post S 14° E 38.65' (m. 38.94')  
Nail & Remon Tag in SW side 18" Maple S 18° E 93.25' (m. 93.00')  
Nail & Remon Tag E'ly side P. pole N 33° E 123.55'  
C/L blacktop road West 5.6'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-8 Standard Kent County Monument

Nail & K.C. remon. tag on N side 28" Basswood S 66° W 56.60'  
NE cor. Garage N 45° W 171.20'  
Nail & K.C. remon. tag on top wood guard rail post (moved) N 90° E 10.65'  
Nail & K.C. remon. tag on top wood guard rail post (moved) S 14° E 38.94'  
Nail & K.C. remon. tag on SW side 18" Maple S 18° E 93.00'  
Nail & K.C. remon. tag on E'ly side P. pole N 33° E 123.55'



Signed by *Randy J. Kolehouse*

Date 7/23/96

Surveyor's Michigan License No. \_\_\_\_\_

25854