

**SURVEY & REMONUMENTATION**

FEB 14 1997

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**KENT COUNTY REMONUMENTATION**

For corners in

Kent (County)	Located in: Gains Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>C-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

*Handwritten signature*

96 AUG -8 AM 8:42

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD

**9232**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Randy Kolehouse, in a field survey on January 22 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5	4	3	2	1						
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C-12	1831	G.L.O. Notes	Mullett	Set Post
	1956	Witness Map	K.C. Surveyor	Concrete Monument
	1973	L.C.R.C. #526	Exxel Engineering	Boat Spike
	1982	L.C.R.C. #3070	Jonker Land Surveys	Fnd. Boat Spike over Conc. Mon. / Set K.C. Monument
	1989	L.C.R.C. #5025	J. Bueche	K.C. Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96

CHAIRMAN *Handwritten signature*

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Jonker Land Surveys on 8/5/82 and was recorded per L.C.R.C. #3070.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-12 Found a Standard Kent County Monument 5' East of the C/L of Eastern Avenue (bit.) running N-S on line of a tree row running West per L.C.R.C.'s #3070 and #5025 as set by Rob Jonker in place of a boat spike he found over a concrete monument.

L.C.R.C. #3070

L.C.R.C. #5025

Remon. tag on NE side 16" Walnut S 60° E 27.81'  
 C/L N-S pvt. 5' W


Nail & Remon Tag NE side 20" Walnut S 60° E 27.81' (m. 27.71')  
 Nail & Remon Tag W side 20" Elm N 10° E 191.71' (m. 191.42')  
 Nail & Remon Tag N side service pole N 65° W 146.33' (m. 148.47')  
 SW cor. conc. R.O.W. marker @ driveway culv N 35° E 24.52' (m. 24.91')  
 C/L blacktop N-S West 5' ±

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-12 Standard Kent County Monument

- Nail & K.C. remon. tag on N side P. pole N 85° E 86.20'
- Nail & K.C. remon. tag on NE side 20" Walnut S 60° E 27.71'
- SW cor. R.O.W. marker (broken) N 35° E 24.91'
- Nail & K.C. remon. tag on W side service pole N 65° W 148.47'



Signed by *Randy J. Kolehouse*

Date 7/23/96

Surveyor's Michigan License No. 25854