

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

For corners in COMMISSION

<u>Kent</u> (County)	Located in: <u>Gaines</u> Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>D-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

96 AUG -8 AM 8:42

REG. OF DEEDS

*Lucy St. Paul*

**9237**

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on January 23 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1						
3												
4	7	3	9	10	11	12						
5												
6	18	17	15	15	14	13						
7		⊙										
8	19	20	21	22	23	24						
9												
10	30	28	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-7	1831	G.L.O. Notes	Mullett	Set Post	P.A. 345 1990 KENT COUNTY
	1963	Witness Map	K.C. Surveyor	1" Pipe	PEER APPROVED <u>3/21/96</u>
	1974	Survey Records	Exxel Engineering	Iron in Mon. Box	CHAIRMAN <u>Randy Kolehouse</u>
	1982	L.C.R.C. #661	J. Clapp	Iron in Mon. Box	
	1982	L.C.R.C. #2917	Exxel Engineering	Fnd. 1" Iron in Mon. Box / Set K.C. Monument	
	1989	L.C.R.C. #5029	J. Bueche	K.C. Monument	

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Exxel Engineering on 6/2/82 and was recorded per L.C.R.C. #2917.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-7 Found a Standard Kent County Monument in a monument box 1' M/L South of the C/L of 84th Street (bit.) running E & W on line of brush row running South per L.C.R.C.'s #681, #2917, #5029 and Exxel Engineering records as set by Exxel Engineering in place of a 1" x 30" iron in a monument box they found which checked L.C.R.C. #661 and K.C. Surveyor's records.

L.C.R.C. #2917

PK & KC tag in E sde P. Pole S 25° W 90.82'  
NW corner I-Beam post N 63° W 43.40'  
PK in KC tag in SE sde P. Pole N 63° E 159.32'

L.C.R.C. #5029

PK & Remon Tag in SE side P. pole N 63° E 159.32' (m. 159.20')  
Nail & Remon Tag in top of guard rail post N 60° W 44.90'  
C/L E-W road North 0.9'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-7 Standard Kent County Monument in a Monument Box

- Nail & K.C. remon. tag on E side 10" Maple N 20° W 41.91'
- Nail & K.C. remon. tag on top guard rail post N 60° W 44.90'
- Nail & K.C. remon. tag on NW side Trip 6" Elm S 55° W 64.83'
- Nail & K.C. remon. tag on W side new P. pole S 25° W 87.61'
- Nail & K.C. remon. tag on SE side P. pole N 63° E 159.20'

Signed by Randy J. Kolehouse  
EARTH TECH

Date 7/23/96

Surveyor's Michigan License No. 25854

