

\$7.00  
\$2.00

JAN 23 1996

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
COMMISSION KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>D-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
95 DEC 28 PM 2:21  
REG. OF DEEDS  
*Lucy Bond*  
8908

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randy Kolehouse, in a field survey on May 16 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-10 This corner was not originally set by the G.L.O.

1903	Survey Notes	Williams & Works	Big Stone and Stake
1973	L.C.R.C. #418	Medema, Van Kooten & Assoc.	Set 3/4" Iron at Int. of 1/4 Lines
1989-1993	Surveys	Exxel Engineering	Set Iron at int. of 1/4 Lines (3.77' South of erroneous MVK Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-10 Found capped Exxel iron at fence intersection running South and West and 3.77' South of MVK iron. Found iron is within 0.2' of intersection of 1/4 lines and is accepted as Center Section.

Survey L. 213 P. 7


- PK W sde T. Pole N10°E 20.87'
- Nail SE sde 11" Hickory S45°W 39.81'
- PK S sde 12" Maple S80°E 28.81'
- Nail N'y sde 28" Maple East 21.40'

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 10/26/95  
CHAIRMAN Harry Huber

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-10 Replaced the capped Exxel iron with a Standard 4" x 30" Kent County Monument.

- PK in W side T. pole N 10° E 20.87'
- Nail in SE side 11" Hickory S 45° W 39.81'
- PK in S side 12" Maple S 80° E 28.81'
- Nail in N'y side 28" Maple East 21.40'



Signed by Randy J. Kolehouse Date 12/22/95  
EARTH TECH

Surveyor's Michigan License No. 25854