

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

For corners in REMONUMENTATION

<u>Kent</u> (County)	Located in: <u>Gaines</u> Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>D-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

95 AUG -8 AM 8:42

REG. OF DEEDS

9239

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on January 23 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

D-11 1831	G.L.O. Notes	Mullett	Set Post	P.A. 345 1990 KENT COUNTY
1958	Witness Map	K.C. Surveyor	Mon. Box	PEER APPROVED 3/7/96
1973	L.C.R.C. #418	Medema, Van Kooten & Assoc.	Iron in Mon. Box	CHAIRMAN <u>Stanley Bueche</u>
1973	L.C.R.C. #509	Exxel Engineering	Iron in Mon. Box	
1980	L.C.R.C. #1743	Williams & Works	Fnd. Iron in Mon. Box / Set K.C. Monument	
1989	L.C.R.C. #5031	J. Bueche	K.C. Monument in Mon. Box	

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 12/23/80 and was recorded per L.C.R.C. #1743.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-11 Found a Standard Kent County Monument in a monument box in the C/L of 100th Street (bit.) running E & W on line of a tree row running N & S per L.C.R.C.'s #509 #1743 and #5031 as set by Williams & Works in place of an iron in a monument box which checked L.C.R.C.'s #418, #509 and K.C. Surveyor's records.

L.C.R.C. #1743

- Nail & K.C. Remon. Tag in West Side 12" Elm N 14° W 53.34'
- Nail & K.C. Remon. Tag in S.W. Side 26" Maple N 62° W 78.90'
- Nail & K.C. Remon. Tag in West Side Power-Tel. Pole South 30.14'
- SE Cor. Hse. #1179 (brick) N 30° W 120.28'
- N.E. Cor. Hse. #1176 (brick) S 50° W 125.54'

L.C.R.C. #5031

- New Nail & Remon Tag in W side 16" Elm N 14° W 53.34' (m. 53.26')
- Nail & Remon Tag in W side power-tel. pole South 30.14'
- Nail & Remon Tag in SW side 40" Oak N 70° W 111.75'
- SE corner Hse #1179 (brick) N 30° W 120.28' (m. 120.05')
- NE corner Hse #1176 (brick) S 50° W 125.54' (m. 125.40')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-11 Standard Kent County Monument in a Monument Box

- Nail & K.C. remon. tag on W side 16" Elm N 14° W 53.26'
- SE cor. hse. #1179 (brick) N 30° W 120.05'
- Nail & K.C. remon. tag on SW side 40" Oak N 70° W 111.75'
- NE cor. hse. #1176 S 50° W 125.40'
- Nail & K.C. remon. tag on W side P. pole South 30.14'



Signed by Randy J. Kolehouse  
EARTH TECH

Date 7/23/96

Surveyor's Michigan License No. 25854