

**SURVEY & REMONUMENTATION**

FEB 14 1997

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**KENT COUNTY REMONUMENTATION**

For corners in **COMMISSION**

Kent (County)	Located in: Gains Township	Corner Code #
1 Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>E-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2 Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3 Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 96 AUG -8 AM 8:42  
 REG. OF DEEDS  
*W. J. ...*  
**9242**  
 Register of Deeds Stamp & File Number

4 Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5 Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on December 29 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A Description of original monument and accessories and/or subsequent restoration:

E-2 1831	G.L.O. Notes	Mullett	Set Post
1962	Witness Map	K.C. Monument	"+" in pavement
1976	L.C.R.C. #931	Exxel Engineering	1/2" Iron in Mon. Box
1982	L.C.R.C. #2920	Exxel Engineering	Fnd. 1/2" Iron in Mon. Box / Set K.C. Monument
1990	L.C.R.C. #5737	J. Bueche	Reset K.C. Monument

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 3/7/96  
 CHAIRMAN *Harry ...*

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5	4	3								
3													
4	7		8	9	10								
5													
6	18		17	16	15								
7													
8	19		20	21	22								
9													
10	30		29	28	27								
11													
12	31		32	33	34								
13													

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Exxel Engineering on 6/4/82 and was recorded per L.C.R.C. #2920.

B Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-2 Found a Standard Kent County Monument in the C/L of Kalamazoo Ave. (bit.) running N & S on line of tree row running E & W per L.C.R.C.'s #2920 and #5737 as reset by J. Bueche in place of a PK nail he found in 1990 which checked the location of the K.C. Mon. set by Exxel Engineering in place of a 1/2" iron in a monument box which checked L.C.R.C. #931 and K.C. Surveyor's records.

L.C.R.C. #2920

L.C.R.C. #5737

Top of steel fence post at South end fence S 89° E 53.55'

Top of steel fence post at South end fence S 89° E 53.55' (m. 50.55')  
 Nail remon. tag in S side P. pole N 35° W 74.50' (m. 74.41')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-2 Standard Kent County Monument

- Nail & K.C. remon. tag on SW side P. pole N 35° W 74.41'
- Nail & K.C. remon. tag on SE side P. pole N 30° E 94.97'
- Nail & K.C. remon. tag on N side P. pole N 85° E 44.55'
- Nail & K.C. remon. tag on NW side P. pole S 25° W 237.77'
- Top of steel fence post at South end fence S 89° E 50.55'

Signed by *Randy J. Kolehouse*  
 EARTH TECH

Date 7/23/96

Surveyor's Michigan License No. 25854

