

SURVEY & REMONUMENTATION

FEB 14 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Gaines Township	Corner Code #
1 Public Land Survey	T <u>5N</u>	R <u>11W</u>	<u>E-6</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2 Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3 Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORDING
 96 AUG -8 AM 8:43
 REG. OF DEEDS
 9246
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on December 29 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-6	1831	G.L.O. Notes	Mullett	Set Post
	1963	Witness Map	K.C. Surveyor	Iron
	1981	L.C.R.C. #1796	William Byl	Fnd. 1" Iron in Mon. Box / Set K.C. Monument in Mon. Box
	1989	L.C.R.C. #5036	J. Bueche	K.C. Monument in Mon. Box

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 3/7/96
 CHAIRMAN Randy Kolehouse

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 2/23/81 and was recorded per L.C.R.C. #1796.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-6 Found a Standard Kent County Monument in a monument box on the C/L of Kalamazoo Avenue (bit.) running N-S on line of a fence row running E & W as set by William Byl in place of a 1" iron they found in the monument box which checked K.C. Surveyor's records.

L.C.R.C. #1796

L.C.R.C. #5036

SW cor. brick veneer on garage of Hse. #8000 W 80° E 164.20'
 Nail & tag, S side 40" Oak East 63.05'
 Nail & tag, W side MBT ple S 10° E 135.90'
 Nail & tag, E side CP pole S 15 W 107.11'


SW corner brick veneer on garage of house #8000 W 80° E 164.20'
 New Nail & Remon. Tag S side 48" Oak East 63.05'
 Nail & Remon. Tag E side CP pole S 15° W 107.11'
 Nail & remon. Tag in W side 18' Oak (stump) N 30° E 107.70'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6 Standard Kent County Monument in a Monument Box

SW cor. brick veneer on garage of hse. #8000 W 80° E 164.20'
 Nail & K.C. remon. tag on S side 48" Oak E 63.05'
 Nail & K.C. remon. tag on E side CP pole S 15° W 107.11'
 Nail & K.C. remon. tag on W side 18" Oak Stump N 30° E 107.70'



Signed by Randy J. Kolehouse
 EARTH TECH

Date 7/23/96

Surveyor's Michigan License No. 25854