

SURVEY & REMONUMENTATION

FEB 14 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in: Gaines Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>E-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

9252

Register of Deeds Stamp & File Number

96 AUG -8 AM 8:43

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Randy Kolehouse, in a field survey on January 19 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-12	1831	G.L.O. Notes	Mullett	Set Post	P.A. 345 1990 KENT COUNTY
	1965	Witness Map	K.C. Surveyor	N/A	PEER APPROVED <u>3/7/96</u>
	1973	L.C.R.C. #419	Medema, Van Kooten & Assoc.	Nail	CHAIRMAN <u>Randy Kolehouse</u>
	1973	L.C.R.C. #509	Exxel Engineering	1/2" Iron	
	1984	L.C.R.C. #3899	William Byl	Fnd. Nail per L.C.R.C. #419 / Set K.C. Monument in Stump	
	1989	L.C.R.C. #5042	J. Bueche	K.C. Monument in Stump	

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 2/16/84 and was recorded per L.C.R.C. #3899.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-12 Found a Standard Kent County Monument in tree stump per L.C.R.C.'s #3899 and #5042 as set by William Byl to replace a nail set in tree which checked L.C.R.C. #419 and K.C. Surveyor's records.

L.C.R.C. #3899	L.C.R.C. #5042
Nail & tag, E sd. 14" Maple N 45° W 13.15'	K.C. Mon on NE side of 24" stump
Nail & tag, W sd. 12" Maple N 05° E 54.62'	Nail & Remon Tag E side 16" Maple N 45° W 18.15'
	Nail & Remon Tag W side 14" Maple N 05° E 54.62' (m. 54.57')
	Nail & Remon Tag S side 26" Maple N 85° E 48.85'
	East edge of woods East 350' ±

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-12 Standard Kent County Monument in Cherry Stump

- Nail & K.C. remon. tag on E side 14" Maple N 10° W 11.09'
- Nail & K.C. remon. tag on E side 16" Maple N 45° W 18.15'
- Nail & K.C. remon. tag on E side 16" Maple S 10° W 64.93'
- Nail & K.C. remon. tag on S side 26" Maple (dead) N 85° E 48.85'
- Nail & K.C. remon. tag on W side 14" Maple N 05° E 54.57'

Signed by Randy J Kolehouse Date 7/23/96
 EARTH TECH

Surveyor's Michigan License No. 25854

