

FEB 14 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

Form with fields: For corners in Kent (County), Located in: Gaines Township, Corner Code #. Includes sections for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

Register of Deeds Stamp & File Number. Includes date 96 AUG -8 AM 8:43, handwritten name Luc S. Bond, and file number 9253.

I, Randy Kolehouse, in a field survey on January 19, 1996, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with 4 columns: E-13 1817, G.L.O. Notes, L. Lyon, Set Post. Includes entries for Witness Map, L.C.R.C. #3391, L.C.R.C. #5043, K.C. Surveyor, William Byl, J. Bueche, Stone, Fnd. Stone / Set K.C. Monument, K.C. Monument.

Note: This corner is not common with E-1, T4N, R11W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 4/20/83 and was recorded per L.C.R.C. #3391.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13 Found a Standard Kent County Monument 7' North of C/L of 108th Street (gravel) running East and 95' East of 8th Street (gravel) running South at old fence line to North per L.C.R.C.'s #3391 and #5043 as set by William Byl in place of a stone they found which checked Williams & Works records and K.C. Surveyor's records.

L.C.R.C. #3391 L.C.R.C. #5043

Table comparing L.C.R.C. #3391 and L.C.R.C. #5043. Columns include monument descriptions like 'Nail & tag, E sd. 12" Walnut N 05° W 56.95'', 'K.C. Mon 10" below surface', etc.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-13 Standard Kent County Monument
Nail & K.C. remon. tag on S side 18" Oak S 65° E 88.67
Nail & K.C. remon. tag on W side 14" Oak S 10° E 53.70'
Nail & K.C. remon. tag on W side 12" Oak S 40 W 58.29'
Nail & K.C. remon. tag on N side 12" Maple N 70° W 37.28'
New Nail & K.C. remon. tag on E side 16" Walnut 7' high N 05° W 56.71'
Allegan Remon. Capped Rebar NE 5, T4N, R11W, West 101.17'

Signed by Randy J. Kolehouse, EARTH TECH, Date 7/23/96, Surveyor's Michigan License No. 25854

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

P.A. 345 1990 KENT COUNTY PEER APPROVED 3/7/96 CHAIRMAN Randy Huber

