

\$7.00
\$2.00

JAN 23 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	F-4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

95 DEC 28 PM 2:21

REG. OF DEEDS
8911

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Randy Kolehouse, in a field survey on May 15 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-4 This corner was not originally set by the G.L.O.

1922	Survey Records	Williams & Works	Iron & Stone
1972	L.C.R.C. #166	Medema, Van Kooten & Assoc.	Set Iron at Intersection of 1/4 Lines
1977	Survey Records	Exxel Engineering	1" Iron

P.A. 345 1990 KENT COUNTY
PEER APPROVED 10/26/95
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-4 Found a 1" iron per L.C.R.C. #166 as set by Medema, Van Kooten & Assoc. near corner of fence running North & East. This iron is within 0.10' of the intersection of 1/4 lines. Checked the following measurements from Williams & Works 1922 survey.

Measure Center to E 1/4 2,568.5' Williams & Works 1922 = 2,657.0'
Measure Center to S 1/4 2,655.8' Williams & Works 1922 = 2,656.2'

Accepted iron as Center Section.

L.C.R.C. #166

- Nail in side of fe post SE 2.10'
- Nail in side of fe post N 9.70'
- Nail in side of P. pole NE 94.6'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-4 Replace 1" iron with Standard 4" x 30" Kent County Monument.

- Nail & K.C. remon. tag in W side of fence post S 01° E 2.10'
- Nail & K.C. remon. tag in W side of fence post North 9.68'
- Nail & K.C. remon. tag in W side P. pole N 15° E 94.63'
- Nail & K.C. remon. tag in N face 12" Cherry East 29.00'



Signed by [Signature]
EARTH TECH

Date 12/22/95

Surveyor's Michigan License No. 25854