

LSUBVY 6
RECORDATION 1991

JAN 23 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>F-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

95 DEC 28 PM 2:23

REG. OF DEEDS
Lucy St. John
8926

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on November 10 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-8 This corner was not originally set by the G.L.O.

?? Survey Records Exxel Engineering Calculated Intersection of 1/4 Lines

No other information on record.
No corner information shown in Kent County Surveyor's records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-8 Set point at the intersection of 1/4 lines. This point is 0.2' North and 0.4' East of Exxel Engineering's calculated location.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/28/95
CHAIRMAN *Harry Huber*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-8 Set a standard 4" x 30" Kent County Monument.

- Nail & K.C. remon. tag in E side 6" Oak N 0° E 12.13'
- Nail & K.C. remon. tag in N side 18" Beech S 6° E 7.91'
- Nail & K.C. remon. tag in NW side 6" Wood Post S 24° W 5.02'
- Nail & K.C. remon. tag in S side 40" Beech S 75° W 20.96'
- Nail & K.C. remon. tag in NE side 8" Oak N 66° W 38.39'
- Fence corner, fences running South and West are 2.5' South and 3.0' West



Signed by *Randy J. Kolehouse* Date 12/22/95
EARTH TECH

Surveyor's Michigan License No. 25854