

**SURVEY & REMONUMENTATION**

FEB 14 1997

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**KENT COUNTY REMONUMENTATION**

For corners in **COMMISSION**

Kent (County)	Located in: Gains Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>F-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD

96 AUG - 8 AM 8:44

REG. OF DEEDS  
*Randy Kolehous*  
 9260

Register of Deeds Stamp & File Number

I, Randy Kolehous, in a field survey on January 25 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-11	1831	G.L.O. Notes	Mullett	Set Post
	1959	Witness Map	K.C. Surveyor	Iron in Mon. Box
	1980	L.C.R.C. #1353	Exxel Engineering	Iron in Mon. Box
	1982	L.C.R.C. #2923	Exxel Engineering	Fnd. Iron in Mon. Box / Set K.C. Monument
	1989	L.C.R.C. #5048	J. Bueche	K.C. Monument

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 3/7/96  
 CHAIRMAN Randy Kolehous

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Exxel Engineering on 6/4/82 and was recorded per L.C.R.C. #2923.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-11 Found a Standard Kent County Monument on C/L of 100th Street (bit.) per L.C.R.C.'s #2923 and #5048 as set by Exxel Engineering in place of a 3/4" iron they found in a monument box which checked L.C.R.C. #1353 and K.C. Surveyor's records.

L.C.R.C. #2923

L.C.R.C. #5048


Nail & KC tag in E sde 14" Maple S 35° W 70.54'	Nail & Remon. Tag in E side 18" Maple S 35° W 70.54' (m. 70.40')
Nail & KC tag in W sde 15" Maple S 05° W 52.50'	Nail & Remon. Tag in W side 18" Maple S 05° W 52.50' (m. 52.35')
Nail & KC tag in NE sde 16" Maple S 18° E 74.76'	Nail & Remon. Tag in NE side 20" Maple S 18° E 74.76' (m. 74.72')
Corner is on C/L E-W road	60 d nail in SW side 16" Maple S 55° E 94.75'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11 Standard Kent County Monument

- Nail & K.C. remon. tag on NE side T. pole N 25° W 217.57'
- 60 d nail on SW side 16" Maple S 55° E 94.75'
- Nail & K.C. remon. tag on NE side 20" Maple S 18° E 74.72'
- Nail & K.C. remon. tag on W side 18" Maple S 05° W 52.35'
- Nail & K.C. remon. tag on E side 18" Maple S 35° W 70.40'



Signed by Randy J. Kolehous Date 7/23/96

Surveyor's Michigan License No. 25854