

SURVEY &
REMONUMENTATION

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in COMMISSION

Kent (County)	Located in:	Gaines Township	Corner Code #
1. Public Land Survey	T <u>5N</u>	R <u>11W</u>	<u>F-12</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

95 AUG -8 AM 8:44

REG. OF DEEDS
Lucy J. Land

9261

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Randy Kolehouse, in a field survey on January 23 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
F-12 This corner was not originally set by the G.L.O.
1986 L.C.R.C. #4460 Exxel Engineering Set Iron


P.A. 345 1990 KENT COUNTY
PEER APPROVED 5/30/96
CHAIRMAN Randy Kolehouse

No other information on record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
F-12 Found a capped iron #12579 as set by Exxel Engineering at the intersection of 1/4 lines, on tree rows running West and North and a field division line running East per L.C.R.C. #4460. Iron is 0.15' West and 0.15' South of intersection of 1/4 lines. Accepted iron as Center of Section.
L.C.R.C. #4460
Spike in W'ly sde 16" Maple South 13.04' (m. 13.02')
Spike in NE sde 10" Cherry N 50° W 13.27' (m. 13.16')
Spike in E sde 4" Maple North 21.32' (m. 21.34')
Spike in SE sde 5" Ash S 50° W 27.23' (m. 27.22')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
F-12 Set a Standard Kent County Monument in Place of Capped Rebar
Nail & K.C. remon. tag on N'ly side 16" Maple South 13.02'
Nail & K.C. remon. tag on NE side 10" Cherry N 50° W 13.16'
Nail & K.C. remon. tag on E side 4" Maple N. 21.34'
Nail & K.C. remon. tag on SE side 5" Ash S 50° W 27.22'



Signed by Randy J. Kolehouse Date 7/23/96
EARTH TECH
Surveyor's Michigan License No. 25854