

SURVEY & REMONUMENTATION

FEB 14 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in: Gaines Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>G-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD

96 AUG - 8 AM 8:44

REG. OF DEEDS
Lucy Bond

9270

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Randy Kolehouse, in a field survey on September 29 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-8	1831	G.L.O. Notes	Mullett	Set Post
	1960	Witness Map	K.C. Surveyor	Iron
	1974	L.C.R.C. #720	P.E. VanKooten	2" Iron
	1977	L.C.R.C. #1225	William Byl	"T" Iron
	1981	L.C.R.C. #1807	William Byl	Fnd. "T" Iron & Pipe / Set K.C. Monument
	1989	L.C.R.C. #5056	J. Bueche	K.C. Monument

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 3/17/96
 CHAIRMAN *Harry Hube*

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 3/30/81 and was recorded per L.C.R.C. #1807.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-8 Found a Standard Kent County Monument on the East edge of two tracks running North 10' North of the South edge of woods per L.C.R.C.'s #1807 and #5056 as set by William Byl in place of a "T" iron and pipe he found which checked L.C.R.C.'s #720, #1225 and the K.C. Surveyor's records.

L.C.R.C. #1807

- Nail & tag, S side 30" Oak N 45 E 40.62'
- Nail & tag, W side 10" Oak N 25 E 22.13'
- Nail & tag, E side 12" Oak N 15 W 47.04'
- Nail & tag, S side 14" Oak N 70 W 34.40'
- Nail & tag, N side 20" Beech East 29.40'

L.C.R.C. #5056

- New Nail & Remon Tag S side 36" Oak N 45° E 40.62'
- Nail & Remon Tag W side 14" Oak N 25° E 22.13'
- Nail & Remon Tag E side 16" Oak N 15° W 47.04'
- Nail & Remon Tag S side 18" Oak N 70° W 34.40'
- South edge woods South 10' ±
- On C/L trail North

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8 Standard Kent County Monument

- Nail & K.C. remon. tag on SE side 32" W Oak N 55° E 40.60'
- Nail & K.C. remon. tag on N side 16" W. Oak N 39° E 22.13;
- Nail & K.C. remon. tag on E side 18" W. Oak N 10° W 47.05'
- Nail & K.C. remon. tag on S side 18" Maple N 65° W 34.34'
- Nail & K.C. remon. tag on SW side 15" B. Oak S 35° W 25.47'
- Nail & K.C. remon. tag on N side 27" stump N 90° E 29.41'

Signed by *Randy J. Kolehouse* Date 7/23/96
 EARTH TECH

Surveyor's Michigan License No. 25854

