

SURVEY & REMONUMENTATION

FEB 14 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

<u>Kent</u> (County)	Located in: <u>Gaines</u> Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>H-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REG. OF DEEDS

Handwritten signature

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 96 AUG -8 AM 8:44

9277

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on January 2 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3								10				
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

H-3	1831	G.L.O. Notes	Mullett	Set Post
	1961	Witness Map	K.C. Surveyor	1" Iron
	1976	L.C.R.C. #931	Exxel Engineering	1/2" Iron in Mon. Box
	1981	L.C.R.C. #2828	Jonker Land Survey	Fnd. 1/2" Iron in Mon. Box / Set K.C. Monument
	1989	L.C.R.C. #5062	J. Bueche	K.C. Monument
	1994	L.C.R.C. #7157	Glaza	K.C. Monument

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 3/7/96
 CHAIRMAN Harry Stur

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Rob Jonker on 4/1/82 and was recorded per L.C.R.C. #2828.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-3 Found a Standard Kent County Monument in the C/L of 68th Street (bit.) running E & W per L.C.R.C.'s #2828, #5062 and #7157 as set by Rob Jonker in place of a 1/2" iron in a monument box he found that checked L.C.R.C. #931 and K.C. Surveyor's records.

L.C.R.C. #2828	L.C.R.C. #5062	L.C.R.C. #7157
Remon. tag on E side p. pole S 12° W 52.6'	Nail & Remon Tag on E side p. pole S 12° W 52.6'	Nail & K.C. remon tag in E side P. pole S 12° W 52.60'
Remon. tag on SW side p. pole N 52° W 103.83'	Nail & Remon Tag on SW side p. pole N 52° W 103.83'	Nail & K.C. remon tag in SW side P. pole N 52° W 103.83'
Remon. tag on W side t. pole N 00° W 39.26' (m. 39.15')	Nail & Remon tag on W side t. pole N 00° W 103.03' (m. 35.15')	Nail & K.C. remon tag in E side T. pole N 00° W 39.15' C/L MH, East along C/L 148.37'
	SW cor. conc. patio N 30° W 87.63'	SW corner of concrete patio N 30° W 87.63'
	SE cor. conc. patio N 35° E 85.60'	SE corner of concrete patio N 35° E 85.60'
		On C/L East-West pavement

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-3 Standard Kent County Monument
 Nail & K.C. remon. tag on E side P. pole S 12° W 52.60'
 Nail & K.C. remon. tag on SW side P. pole N 52° W 103.83'
 Nail & K.C. remon. tag on E side T. pole N 00° W 39.15'
 SE cor. conc. patio N 35° E 85.60'
 SW cor. conc. patio N 30° W 87.63'

Signed by Randy J. Kolehouse Date 7/23/96

Surveyor's Michigan License No. 25854

