

SURVEY & REMONUMENTATION

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

<u>Kent</u> (County)	Located in: <u>Gaines</u> Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>H-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 96 AUG -8 AM 8:44
 REG. OF DEEDS
Lucy St...
9278
 Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on January 2 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-5	1831	G.L.O. Notes	Mullett	Set Post
	1950	Survey Records	Williams & Works	Iron
	1972	L.C.R.C. #166	Medema, Van Kooten & Assoc.	Fnd. 1" Iron / Set K.C. Monument
	1981	L.C.R.C. #1795	William Byl	Fnd. 1" Iron / Set K.C. Monument
	1989	L.C.R.C. #5063	J. Bueche	K.C. Monument
	1994	L.C.R.C. #7155	Glaza	K.C. Monument

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 3/7/96
 CHAIRMAN *Randy Kolehouse*

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 2/24/81 and was recorded per L.C.R.C. #1795.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-5 Found a Standard Kent County Monument 2.5' South of the C/L of 72nd Street (bit.) running E & W on line of tree row running North per L.C.R.C.'s #1795, #5063 and #7155 as set by William Byl in place of a 1" iron he found that checked L.C.R.C. #166 and Williams & Works' survey records.

L.C.R.C. #1795	L.C.R.C. #7155
Nail & tag, W side Transformer pole N 67.73'	Nail & K.C. remon tag in W side transformer pole North 67.73'
L.C.R.C. #5063	Nail & K.C. remon tag in N side T. pole S 80° W 109.32'
Nail & Remon Tag in W side Transformer pole North 67.73'	Nail & K.C. remon tag in N side P. pole S 82° E 183.06'
Nail & Remon Tag in N side t. pole S 80° W 109.32'	Nail & K.C. remon tag in S'ly side 10" tree N 75° W 191.87'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5 Standard Kent County Monument

Nail & K.C. remon. tag on W side Transformer pole North 67.73'
 Nail & K.C. remon. tag on N side T. pole S 80° W 109.32'
 Nail & K.C. remon. tag on N side P. pole S 82° E 183.06'
 Nail & K.C. remon. tag on S side 10" Tree N 75° W 191.87'

Signed by *Randy J. Kolehouse* Date 7/23/96

Surveyor's Michigan License No. 25854

