

**SURVEY & REMONUMENTATION**

FEB 14 1997

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**KENT COUNTY REMONUMENTATION**

**COMMISSION**

For corners in

<u>Kent</u> (County)	Located in: <u>Gaines</u> Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>H-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on January 2 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

H-7	1831	G.L.O. Notes	Mullett	Set Post
	1961	Witness Map	K.C. Surveyor	"T" Iron
	1971	L.C.R.C. #34	Williams & Works	"T" Iron
	1972	L.C.R.C. #263	Medema, Van Kooten & Assoc.	Iron in Mon. Box
	1981	L.C.R.C. #1802	William Byl	Fnd. Iron in Mon. Box / Set K.C. Monument
	1989	L.C.R.C. #5064	J. Bueche	K.C. Monument
	1994	L.C.R.C. #7171	Glaza Assoc.	K.C. Monument

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 3/7/96  
 CHAIRMAN 3/7/96

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 2/24/81 and was recorded per L.C.R.C. #1802.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

H-7 Found a Standard Kent County Monument in the C/L of 84th Street (bit.) running East & West per L.C.R.C.'s #1802, #5064 and #7171 as set by William Byl in place of an iron in a monument box he found that checked L.C.R.C.'s #34 and #263 which checked the same location of "T" iron per Williams & Works' 1961 survey records.

L.C.R.C. #1802	L.C.R.C. #5064	L.C.R.C. #7171
Nail & tag, N side MBT pole S 50° W 49.00'	Nail & Remon Tag N side MBT pole S 50° W 49.00'	Nail & K.C. remon tag in NW side MBT pole S 50° W 49.00'
Nail & tag, N side Transformer pole N 05° W 47.24'	Nail & Remon Tag W side Transformer pole N 05° W 47.24'	Nail & K.C. Remon tag in W side transformer pole N 05° W 47.24'
Nail & tag, W side 10" Elm S 30° E 57.06'	New Nail & Remon Tag W side 18" Willow S 30° E 57.03'	Nail & K.C. remon tag in W side 24" Willow S 30° E 57.08' (m. 57.10')
NE Corner foundation Hse #2806 (at ground level) S 40° E 57.06' (m. 145.28)	NE corner foundation Hse #2806 (at ground level) S 40° E 145.25' (m. 145.28)	NE corner foundation house #2806 (at ground level) S 40° E 145.25' (m. 145.28')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

H-7 Standard Kent County Monument

- Nail & K.C. remon. tag on NW side MBT pole S 50° W 49.00'
- Nail & K.C. remon. tag on W side Transformer pole N 05° W 47.24'
- Nail & K.C. remon. tag on W side 24" Willow S 30° E 57.10'
- NE cor. fndn. hse. #2806 at ground level S 40° E 145.28'

Signed by Randy J. Kolehouse Date 7/23/96  
 Surveyor's Michigan License No. 25854

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 95 AUG -8 AM 8:45  
 REG. OF DEEDS  
Randy Kolehouse  
**9279**  
 Register of Deeds Stamp & File Number

