

CONVEY &  
REMONUMENTATION

FEB 14 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in: Gains Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>H-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

96 AUG -8 AM 8:45

REG. OF DEEDS  
*[Signature]*  
9280

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on January 3 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	19	18	17	16	15	14	13	12	11	10	9	8	7
9													
10	30	29	28	27	26	25							
11													
12	31	30	29	28	27	26	25	24	23	22	21	20	19
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-9	1831	G.L.O. Notes	Mullett	Set Post	P.A. 345 1990 KENT COUNTY
	1913-1966	Survey Records	Williams & Works	RR Spike & Iron	PEER APPROVED 3/7/96
	1973	L.C.R.C. #600	Medema, Van Kooten & Assoc.	RR Spike	CHAIRMAN <i>[Signature]</i>
	1981	L.C.R.C. #1803	William Byl	1" Iron Over 2" Iron / Set K.C. Monument	
	1989	L.C.R.C. #5065	J. Bueche	K.C. Monument	
	1994	L.C.R.C. #7172	Glaza Assoc.	K.C. Monument	

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 2/24/81 and was recorded per L.C.R.C. #1803.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-9 Found a Standard Kent County Monument 7' M/L South of the center line of 92nd Street (bit.) running East & West per L.C.R.C.'s #1803, #5065 and #7172 as set by William Byl in place of a 1" iron over a 2" iron above a 1" iron bar surrounded by stones he found that check L.C.R.C. #600 and K.C. Surveyor's records.

L.C.R.C. #1803	L.C.R.C. #5065	L.C.R.C. #7172
Nail & tag, S side P. pole N 60° E 120.54'	Nail & Remon Tag W side p. pole South 18.57'	Nail & K.C. remon tag in S side P. pole N 60° E 120.38'
	Nail & Remon Tag S side p. pole N 60° E 120.38'	Nail & K.C. remon tag in N side 42" Willow S 50° E 64.82'
		Nail & K.C. remon tag in E side P. pole S 00° W 18.54'
		Nail & K.C. remon tag in N side 8" Spruce S 74° W 100.15'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-9 Standard Kent County Monument
- Nail & K.C. remon. tag on NW side 8" Spruce S 15° E 60.09'
  - Nail & K.C. remon. tag on S side P. pole N 60° E 120.38'
  - Nail & K.C. remon. tag on N side 42" Willow S 50° E 64.82'
  - Nail & K.C. remon. tag on E side P. pole S 00° W 18.54'
  - Nail & K.C. remon. tag on N side 8" Spruce S 74° W 100.15'

Signed by *Randy J. Kolehouse* Date 7/23/96  
EARTH TECH  
Surveyor's Michigan License No. 25854

