

SURVEY & REMONUMENTATION

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in **COMMISSION**

Kent (County)	Located in: Gains Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>H-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD

95 AUG -8 AM 8:45

REG. OF DEEDS
Lucy Bond

9284

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Randy Kolehouse, in a field survey on January 3 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13	1817	G.L.O. Notes	L. Lyon	Set Post
	1954	Notes	Williams & Works	"T" Iron
	1960	Witness Map	K.C. Surveyor	N/A
	1983	L.C.R.C. #3578	William Byl	Fnd. "T" Iron / Set K.C. Monument
	1989	L.C.R.C. #5067	J. Bueche	K.C. Monument
	1994	L.C.R.C. #7185	Glaza & Associates	K.C. Monument

Note: This corner is not common with H-1, T4N, R11W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 9/29/83 and was recorded per L.C.R.C. #3578.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 Found a Standard Kent County Monument on line of tree row running South per L.C.R.C.'s #3578, #5067 and #7185 as set by William Byl in place of a "T" iron he found which checked Williams & Works' survey records from 1954.

L.C.R.C. #3578	L.C.R.C. #5067	L.C.R.C. #7185
Nail & tag, N sd. 12" Hickory S 75 W 70.70'	New Nail & Remon Tag N side 18" Hickory S 75° W 70.70'	New Nail & Remon Tag N side 18" Hickory S 75° W 70.70'
Nail & tag, W sd. Power pole 00 E 65.08'	Nail & Remon Tag W side p. pole N 00° E 65.08'	Nail & Remon Tag W side p. pole N 00° E 65.08'
Nail & tag, S sd. 30" Maple S 50 E 42.15'	Nail & Remon Tag S side 34" Maple S 50° E 42.15'	Nail & Remon Tag S side 34" Maple S 50° E 42.15'
Nail & tag, N sd. 30" Maple S 70 E 72.15'	Nail & Remon Tag N side 34" Maple S 70° E 72.15'	Nail & Remon Tag N side 34" Maple S 70° E 72.15'
N 1/4 cor. Sec. 3, 4-11, (T-iron) N 90 W 58.92'	N 1/4 cor. Section 3, 4-11, (T-iron) N 90° W 58.92'	N 1/4 corner, Sec. 3, 4-11, (T-iron) N 90° W 58.92'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 Standard Kent County Monument

- Nail & K.C. remon. tag on N side 18" Hickory S 75° W 70.70'
- Nail & K.C. remon. tag on W side P. pole N 00° E 65.08'
- Nail & K.C. remon. tag on S side 34" Maple S 50° E 42.15'
- Nail & K.C. remon. tag on N side 34" Maple S 70° E 72.15'
- N 1/4 cor. Sec. 3, T4N, R11W (T-iron) N 90° W 58.92'

Signed by Randy J. Kolehouse
 EARTH TECH

Date 7/23/96

Surveyor's Michigan License No. 25854

