

# SURVEY & REMONUMENTATION

SEP 03 1999

## SECTION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in: Gaines Township	Corner Code #	
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>1-7</u>	
	T _____ R _____		
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORDS  
 96 AUG -8 AM 8:45  
 REG. OF DEEDS  
*Lucy Bond*

9291

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on December 27 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

I-7	1831 G.L.O. Notes	Mullet	Set Post	
	1930 Witness Map	K.C. Surveyor	"+" in Pavement	P.A. 345 1990 KENT COUNTY
	1961 Witness Map	K.C. Surveyor	PK in "+"	PEER APPROVED <u>3/27/96</u>
	1971 L.C.R.C. #34	Williams & Works	Iron in Mon. Box	CHAIRMAN <u>Randy Kolehouse</u>
	1972 L.C.R.C. #263	Medema, Van Kooten & Assoc.	Iron in Mon. Box	
	1981 L.C.R.C. #1808	William Byl	Fnd. Iron in Mon. Box / Set K.C. Monument	
	1994 L.C.R.C. #7168	Glaza & Associates	K.C. Monument	

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 2/24/81 and was recorded per L.C.R.C. #1808.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I-7 Found a Standard Kent County Monument in a monument box 1' M/L East of the C/L of Hanna Lake Avenue (bit.) running N & S on the C/L of 84th Street (bit.) running E & W per L.C.R.C.'s #1808 and #7168 as set by William Byl in place of a 1" iron in a monument box he found that checked L.C.R.C.'s #34 and #263.

L.C.R.C. #1808

- Nail & tag, W side Power pole N 35 W 93.55'
- Nail & tag, W side Power pole N 35 E 81.40'
- NE cor. foundation (@ ground level) House, S 45 W 164.56'

L.C.R.C. #7168

- Nail & K.C. remon tag in W side P. pole N 35° W 93.55'
- NE corner foundation of house (at ground level) S 45° W 164.56'
- Nail & K.C. remon tag in NW side guy pole S 50° W 45.80'
- Nail & K.C. remon tag in NW side guy pole N 40° E 43.39'
- Nail & K.C. remon tag in W side P. pole N 30° E 80.34'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-7 Standard Kent County Monument in a Monument Box

- Nail & K.C. remon. tag on W side P. pole N 35° W 93.55'
- Nail & K.C. remon. tag on W side P. Pole N 30° E 80.34'
- Nail & K.C. remon. tag on NW side Guy pole S 50° W 45.80'
- Nail & K.C. remon. tag on NW side Guy pole N 40° E 43.39'
- NE cor. fndn. of house at ground level N 45° W 164.56'

Signed by *Randy J. Kolehouse* Date 7/23/96  
 EARTH TECH  
 Surveyor's Michigan License No. 25854

